

GOVERNMENT OF INDIA
OFFICE OF THE EXECUTIVE ENGINEER
CENTRAL WATER COMMISSION
DAMODAR DIVISION, APCAR GARDEN(WEST)
ASANSOL-713304

No.DD/HQ/NIQ/2010-11/1414-22

Dated 12 /07/11

NOTICE INVITING QUOTATIONS

Sealed Quotations are hereby invited by the undersigned on behalf of the President of India from the local / reputed agencies to quote their rates of the following works:

The quotations should reach to this office either by post or by hand or by dropping in to the tender box up to 15.00 hrs. of 21.07.11 and the same will be opened on the same day at 15.30 hrs. in presence of agencies or their authorized representatives, who may be interested to be present at the time of opening of the quotations. Rates should be quoted both in words and figures. Cutting & overwriting, if any, should be attested.

S N	Sub-head and items of work	Qty.	Unit	Supplied Rate	Quoted Rate
Providing, fitting and fixing of Iron Gate at Midnapore.					
1.	Dismantling of old broken gate and disposal of waste and unserviceable material at lead of 100m and lift of 3m.	LS		3000.00	
2.	Earth work in excavation manually in foundation trenches (not exceeding 1.5m in width and 10 Sqm. on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. in all kinds of soil.	0.54	Cum	103.40	
3.	Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete.	0.07	Cum	301.50	
4.	Brick soling with F.P.S. bricks of class designation 75 in foundation and shuttering. All works in foundation up to plinth level.	0.07	Cum	2000.00	
5.	1:2:4 PCC work of specified grade excluding the cost of centering and shuttering, all works in foundation up to plinth level.	0.11	Cum	3257.45	
6.	Centering & Shuttering including strutting, propping etc. & removal of form PCC work for foundations, footings.	0.36	Sqm	119.25	
7.	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in 1:6 Cement mortar.	0.23	cum	2121.75	
8.	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level up to mV floor in all shape & size in 1:6 Cement mortar.	0.64	Cum	2430.30	
9.	12mm cement plaster finished with a floating coat of neat cement of mix. 1:3 in fine sand.	6.98	Sqm	107.80	
10.	Providing, fitting and fixing of iron gate of 1.85mx2.6m in size and 12mm thick with 0.10m x 20cm bracket including providing & fitting of Kabja, Kunda, Handle & Locking system arrangement as per direction of Engineer in charge.	4.81	Sqm	3000.00	

Add 62% for price escalation for West Midnapur which is approved by the CE, EZ-1, CPWD, Kolkatta on 27.01.11.

Terms and Condition:

1. Works should be completed as per drawing, specification & direction of Engineer-in-Charge.
2. Works should be completed within 30 days from the date of issue of work order.
3. Payment will be made through A/C Payee Cheque / Demand Draft on submission of bills in triplicate after satisfactory completion of works.
4. The undersigned reserves the right to reject or accept any or all quotations without assigning any reason thereof.

Sd/-

(Ram Nath Yadav)

Executive Engineer

Copy for information with request to to paste on his office notice board :-

1. The Director, SMD, CWC, New Delhi w.r.t. his letter dated: 29.06.2005.
2. The SE, HOC, CWC, Maithon.
3. The EE, LG Division, CWC, Berhampur.
4. The AAO, Account Branch, Damodar Division, CWC, Asansol.
5. SDE, CWC, Kolkatta/Mednapur/Suri/Durgapur.Tenughat with instruction to paste on his notice board.