

भारत सरकार / Govt. of India
केन्द्रीय जल आयोग / Central Water Commission
अधिषासी अभियंता का कार्यालय / Office of the Executive Engineer
पूर्वी नदियों मंडल / Eastern Rivers Division
प्राची तरंगिनी भवन , प्लॉट संख्या ए 13 और 14 / Plot No.A-13 & 14
प्राची तरंगिनी भवन / Prachi Tarangini Bhawan
पोस्ट : भोई नगर / Bhoi Nagar
भुवनेश्वर / Bhubaneswar - 751022

No. ERD/AB/NIQ/11/803-06

Dated : 09-06-2011

NOTICE INVITING QUOTATION

On behalf of the President of India, sealed quotations are invited for the following works by the undersigned from the bonafide/Govt. approved firms as per the following terms and conditions on or before 3.00 P.M. of 18-06-2011. The quotation will be opened on the same day at 3.30 P.M.

Sl.	Description of work	Quantity	Unit Rate	Amount in Rs.
	Name of work : Renovation and repairing to site office at Talcher G&D site.			
1	Demolishing of lime concrete manually / by mechanical means and disposal of material within 50 metres lead as per direction of engineer-in-charge. 1:3:6 or richer mix	2.836 Cum.		
2	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cent slurry, but the cost of nosing of steps etc. complete as per directed by engineer. 40 mm thick with 20 mm nominal size stone aggregate	70.90 Sqm.		
3	Providing asbestos cement 6 mm thick corrugated sheets roofing and fixing with polymer coated J, or L hooks bolts and nuts 8 mm dia G.I. plain bitumen washers complete excluding the cost of purlins, rafters and trusses : corrugated sheets. Upto 60 degrees pitch including removal of old sheets.	6 No.		
4	Dismantling barbed wire or flexible wire rope in fencing including making rolls and stacking within 50 metres lead as per directed by engineer.	90 kg		
5	Excavating holes upto 0.5 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20 m in depth, including consolidating each deposited by ramming, watering etc. disposing of surplus excavated soils, as directed within a lead of 50 m and lift upto 1.5 m.			
i	All kinds of soils	30 each		
ii	Ordinary rock	10 each		
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work upto plinth level : 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	0.43 Cum.		

PTO

7	Supplying at site angle iron post and strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia etc. complete as per directed by engineer.	406 Kg.		
8	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15 th post, last but one end post and corner post shall be shuttered on both sides and who diagonals interwoven with horizontal wires, of barbed wire 9.38 kg per 100 m (minimum) between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete as per directed by engineer. (cost of posts, struts, earthwork and concrete work to be paid for separately) : payment to be made per metre cost of total length of barbed wire used. With G.I. barbed wire	90 m		
	Total			

Terms & Conditions :-

1. The rates are to be quoted F.O.R. destination inclusive of packing forwarding, freight, insurance and complete installation, if any, at site Talcher.
2. The rates shall be valid for 90 days minimum from the date of opening of the quotation.
3. The above work should be completed within 40 days.
4. The rates are to be quoted in figures as well as in words.
5. The quoted rates should be inclusive of all taxes.
6. Xerox copy of PAN card is compulsory.
7. The undersigned reserves the right to reject a part or the whole of tender without assigning any reason thereof.
8. The envelope containing quotation should be superscribed "Quotation for Renovation & Repairing at site Talcher, due on 18/06/2011.

Sd/-
Executive Engineer
For and on behalf of President of India

Copy to :-

1. The Notice Board, E.R. Division, CWC, Bhubaneswar.
2. The Director, Software Management Directorate, 628, Sewa Bhawan (South), R.K.Puram, New Delhi-110066 along with soft copy (floppy) for publishing in the CWC website and also sent through email at smdte@.nic.in.
3. The Sub-Divisional Engineer, Brahmani Sub-Division, CWC, Rourkela..
4. Jr. Engineer (HQS), Eastern Rivers Division, CWC, Bhubaneswar for information.