

GOVERNMENT OF INDIA
CENTRAL WATER COMMISSION
OFFICE OF THE EXECUTIVE ENGINEER
DAMODAR DIVISION, APCAR GARDEN (WEST)
ASANSOL-713304

No. DD/DB/Tender/2011-12 / 1520-31

dated :- 06 / 08/2011

NOTICE INVITING TENDER

On behalf of The President of India, the under signed invites Sealed tender from the reputed /registered experienced agency for the following work. Contractor are requested to submit their tenders in the official tender box or through registered post upto 1500 hrs on 25/08/2011

S.No	Description of work	Estimated Amount	Earnest Money (refundable)	Cost of Tender in Rs.	Period of contract
Construction of Site Office					
1	Jamalpur	Rs. 4,92,520/-	Rs. 9,850/-	Rs. 500/- in cash	90(Ninety) days
2	Nandadih	Rs. 4,67,760/-	Rs. 9,360/-	-do-	- do -
Extension of Site office					
3	Ramgarh	Rs. 4,67,760/-	Rs. 9,360/-	-do-	- do -

The above tender will be opened at 15.30 Hrs. on the same day. Earnest money in favour of Executive Engineer, Damodar Division, Central Water Commission, Asansol as prescribed in the tender documents should be deposited with the tender in the Form of D.C.R. issued from any nationalized bank/ cash. The tender of the agency who do not deposit earnest money in the prescribed manner are liable to be rejected.


A complete set of tender document of the above work containing detailed terms and conditions, Schedule of quantity can be obtained by the eligible agencies from the office of the undersigned up to 1600 Hrs. on 24/08/2011 on all working days between 11.00 A.M. to 4.00 P.M. on submission of written application up to 16.00 Hrs. on 23/08/2011.

In case of above date of receiving and opening date of tender is declared holiday etc. the tender shall be received & opened on the next working day as per schedule time. More details are available on web site cwc-tender@mail.nic.in & smdte@nic.in.


(RAM NATH YADAV)
EXECUTIVE ENGINEER

Copy along with enclose forwarded for information with request for board publicity through pasting on his office Notice board:-

- ✓ 1. The Director, SMD, CWC, New Delhi is requested to get published in CWC web site. Email for this purpose has already been sent.
2. The SE, HOC, CWC, Maithon Dam (Jharkhand).
3. The E.E. Lower Ganga Division, CWC, Berhampore.
4. The S.D.E, Tenughat/Maithon/Midnapore/Suri/Durgapur/ Kolkata
5. The A.D. II, Head Quarter, Damodar Division, CWC, Asansol.
6. The AAO, A / B, Damodar Division, CWC, Asansol.
7. Notice Board, Damodar Division, CWC, Asansol


(RAM NATH YADAV)
EXECUTIVE ENGINEER

ANNEXTURE – I

DETAILS

- | | | |
|----|---|---|
| 1 | Name of work | Construction & Extension of Site Office |
| 2 | Estimated Amount | :-Rs. . 4,92,520/-(Rupees four lakh ninety two thousand five hundred twenty) only for SL.No 1 , Rs. 4,67,760/-/(Rupees four lakh sixty seven thousand seven hundred sixty) only for SL. No. 2 & 3 |
| 3 | Cost of tender Document | :-Rs. 500/- (Rupees five hundred) only |
| 4 | Earnest Money | :-Rs. . 9,850/-/(Rupees Nine thousand eight hundred fifty) only for SL.No 1 and Rs. 9,360/- Rupees Nine thousand three hundred sixty) only for SL. No. 2&3. |
| 5 | Security Deposit | :- 05 % of the gross value of work shall be deducted from the final bill. |
| 6 | Performance Guarantee | :- 5 % on the work order amount shall be deposited before commencement of work |
| 7 | Time completion of work | :- 90 (Ninety) days from 7 th date of issue of work order |
| 8 | Last date of receipt of application for issue of tender | :- 23/08/.2011 upto 16.00 Hrs |
| 9 | Last date of sale of tender | :- Up to 16.00 Hrs. on 24/08/.2011 |
| 10 | Last date of receiving of tender | :- Upto 15.00 on 25/08/.2011 |
| 11 | Date of opening tender | :- On 25/08/.2011 at 15.30 hrs.
(if the opening date of tender happens to be a holiday under any circumstance the tender will be opened on the next working day at the same time) |
| 12 | Contractor can visit the working site before quoting rates for tender to assess the quantum of work if required | |



EXECUTIVE ENGINEER

SCHEDULE

Name of work :- **Construction of Site office**, Jamalpur

Sl. No	Sub-head and item of work	Qty.	Unit	JAMALPUR	
				Rate supplied	quoted by agency
1	Earth work in excavation manually in foundation trenches (not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil.	28.65	Cum	103.40	
2	Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete.	7.14	Cum	301.50	
3	Brick Soling with Jhama brick/ khoa of 15 cm rammed to 10 cm including watering as per direction of Engineer in charge.	7.14	Cum	4000.00	
4	Providing and laying position cement concrete of specified grade excluding the cost of centering and shuttering – all work upto plinth 1:2:4 cement mortar.	4.08	Cum	3149.10	
5	Brick work with FPS brick of class designation 75 in foundation and plinth in 1:6 Ce,ment Morter.	19.48	Cum	2121.75	
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation , etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m.	5.92	Cum	45.70	
7	Providing and laying damp proof course 40mm thick with Cement concrete 1:2:4	10.68	Sqm	144.15	
8	Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6.	36.19	Cum	2430.30	
9	RCC work in wall (any thickness) including attached pilasters,buttresses,plinth and string course, fillets columns, pillar, pairs,abutments etc. upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.	3.80	Cum	3720.00	
10	RCC work in beams suspended floors, roofs having slope up to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.	7.41	Cum	3673.85	
11	Reinforcement for RCC work including strightning,cutting,bending, placing in position and binding all complete.Mild steel and Medium Tensile steel bars.	1029	Kg	41.50	
12	Centering and shuttering including strutting propping etc.and removal of form for foundation, footing, bases of column etc. for mass concrete.	4.05	Sqm	119.25	
13	Centering and shuttering including strutting propping etc.and removal of form for Columns, pillars etc.	37.80	Sqm	238.40	
14	Centering and shuttering including strutting propping etc.and removal of suspended floors, roofs, landing balconies and access platform.	42.45	Sqm	187.35	
15	Centering and shuttering including strutting propping etc.and removal of form lintels, beams.plinth beam, girders,bressments and cantilevers.	20.47	Sqm	162.55	
16	Cement concrete flooring 1:2:4 finishing with a floating of next cement including cement slurry, but excluding the cost of nosing of steps etc. complete.	39.63	Cum	192.95	
17	Cement plaster (in fine sand) 20mm thick cement plaster of Mix 1:6	191.44	Sqm	95.10	

Contd. ... 2

Sl. No	Sub- head and item of work	Qty.	Unit	Jamalpur	
				Rate supplied	quoted by agency
18	Cement plaster skirting (upto 30cm) with cement mortar 1:3 finished with a floating coat of neat cement 18mm thick.	24.66	Sqm	168.50	
19	Providing and fixing water closer squatting pan (Indian type WC pan) with 100 mm sand cast iron P or S trap level white PVC flushing cistern with manually controlled device (handle lever) conforming to IS :7231 with all fittings and fixtures complete including cutting and making good the walls and floor wherever required white vitreous China Orissa pattern WC pan of size 580X 440mm with flush and integrated type foot rests.	1	each	2304.65	

Remarks : Add 62% for **Jamalpur** under West Midnapore Region approved by CE, CPWD, Kolkata dated 27.01.2011 due to price escalation. Except Sl. No. 3.

Authority of issuing the Tender

212/618

Stamp with Signature.

SCHEDULE

Name of work :- **Construction of Site office, Nandadih,**

Sl. No	Sub-head and item of work	Qty.	Unit	Nandadih	
				Rate supplied	quoted by agency
1	Earth work in excavation manually in foundation trenches (not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil.	28.65	Cum	103.40	
2	Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete.	7.14	Cum	301.50	
3	Brick Soling with Jhama brick/ khoa of 15 cm rammed to 10 cm including watering as per direction of Engineer in charge.	7.14	Cum	4000.00	
4	Providing and laying position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth 1:2:4 cement mortar.	4.08	Cum	3149.10	
5	Brick work with FPS brick of class designation 75 in foundation and plinth in 1:6 Cement Morter.	19.48	Cum	2121.75	
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation , etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m.	5.92	Cum	45.70	
7	Providing and laying damp proof course 40mm thick with Cement concrete 1:2:4	10.68	Sqm	144.15	
8	Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6.	36.19	Cum	2430.30	
9	RCC work in wall (any thickness) including attached pilasters, buttresses, plinth and string course, fillets columns, pillar, pairs, abutments etc. upto floor V level excluding the cost of centering, shuttering, finishing and reinforcement.	3.80	Cum	3720.00	
10	RCC work in beams suspended floors, roofs having slope up to 15 landings, balconies, shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering, shuttering, finishing and reinforcement.	7.41	Cum	3673.85	
11	Reinforcement for RCC work including strightning, cutting, bending, placing in position and binding all complete. Mild steel and Medium Tensile steel bars.	1029	Kg	41.50	
12	Centering and shuttering including strutting propping etc. and removal of form for foundation, footing, bases of column etc. for mass concrete.	4.05	Sqm	119.25	
13	Centering and shuttering including strutting propping etc. and removal of form for Columns, pillars etc.	37.80	Sqm	238.40	
14	Centering and shuttering including strutting propping etc. and removal of suspended floors, roofs, landing balconies and access platform.	42.45	Sqm	187.35	
15	Centering and shuttering including strutting propping etc. and removal of form lintels, beams, plinth beam, girders, bressments and cantilevers.	20.47	Sqm	162.55	
16	Cement concrete flooring 1:2:4 finishing with a floating of next cement including cement slurry, but excluding the cost of nosing of steps etc. complete.	39.63	Cum	192.95	
17	Cement plaster (in fine sand) 20mm thick cement plaster of Mix 1:6	191.44	Sqm	95.10	

Contd. ... 2

Sl. No	Sub- head and item of work	Qty.	Unit	Nandadih	
				Rate supplied	quoted by agency
18	Cement plaster (in fine sand) 12mm thick cement plaster of Mix 1:6	129.83	Sqm	67.65	
19	Cement plaster skirting (upto 30cm) with cement mortar 1:3 finished with a floating coat of neat cement 18mm thick.	24.66	Sqm	168.50	
20	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade on new work (two/ more coats) over & including priming coat with cement primer.	191.44	Sqm	41.55	
21	Finishing wall with water proofing cement paint of required shed new work (two or more) coats applied @ 3.84 Kg/10Sqm.	129.83	Sqm	30.80	
22	Providing and fixing water closer squatting pan (Indian type WC pan) with 100 mm sand cast iron P or S trap level white PVC flushing cistern with manually controlled device (handle lever) conforming to IS :7231 with all fittings and fixtures complete including cutting and making good the walls and floor wherever required white vitreous China Orissa pattern WC pan of size 580X 440mm with flush and integrated type foot rests.	1	each	2304.65	

Remarks : Add 43% for **Nandadih** under Jharkhand Region approved by CE, CPWD, Patna dated 12.01.2011 due to price escalation. Except Sl. No. 3

Authority of issuing the Tender



Stamp with Signature.

SCHEDULE

Name of work :- **Extension of Site office**, Ramgarh.

Sl. No	Sub-head and item of work	Qty.	Unit	Ramgarh	
				Rate supplied	quoted by agency
1	Earth work in excavation manually in foundation trenches (not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil.	28.65	Cum	103.40	
2	Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete.	7.14	Cum	301.50	
3	Brick Soling with Jhama brick/ khoa of 15 cm rammed to 10 cm including watering as per direction of Engineer in charge.	7.14	Cum	4000.00	
4	Providing and laying position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth 1:2:4 cement mortar.	4.08	Cum	3149.10	
5	Brick work with FPS brick of class designation 75 in foundation and plinth in 1:6 Ce,ment Morter.	19.48	Cum	2121.75	
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation , etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m.	5.92	Cum	45.70	
7	Providing and laying damp proof course 40mm thick with Cement concrete 1:2:4	10.68	Sqm	144.15	
8	Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6.	36.19	Cum	2430.30	
9	RCC work in wall (any thickness) including attached pilasters,buttresses,plinth and string course, fillets columns, pillar, pairs,abutments etc. upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.	3.80	Cum	3720.00	
10	RCC work in beams suspended floors, roofs having slope up to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.	7.41	Cum	3673.85	
11	Reinforcement for RCC work including strightning,cutting,bending, placing in position and binding all complete.Mild steel and Medium Tensile steel bars.	1029	Kg	41.50	
12	Centering and shuttering including strutting propping etc.and removal of form for foundation, footing, bases of column etc. for mass concrete.	4.05	Sqm	119.25	
13	Centering and shuttering including strutting propping etc.and removal of form for Columns, pillars etc.	37.80	Sqm	238.40	
14	Centering and shuttering including strutting propping etc.and removal of suspended floors, roofs, landing balconies and access platform.	42.45	Sqm	187.35	
15	Centering and shuttering including strutting propping etc.and removal of form lintels, beams.plinth beam, girders,bressments and cantilevers.	20.47	Sqm	162.55	
16	Cement concrete flooring 1:2:4 finishing with a floating of next cement including cement slurry, but excluding the cost of nosing of steps etc. complete.	39.63	Cum	192.95	
17	Cement plaster (in fine sand) 20mm thick cement plaster of Mix 1:6	191.44	Sqm	95.10	

Contd. ... 2

Sl. No	Sub- head and item of work	Qty.	Unit	Ramgarh	
				Rate supplied	quoted by agency
18	Cement plaster (in fine sand) 12mm thick cement plaster of Mix 1:6	129.83	Sqm	67.65	
19	Cement plaster skirting (upto 30cm) with cement mortar 1:3 finished with a floating coat of neat cement 18mm thick.	24.66	Sqm	168.50	
20	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade on new work (two/ more coats) over & including priming coat with cement primer.	191.44	Sqm	41.55	
21	Finishing wall with water proofing cement paint of required shed new work (two or more) coats applied @ 3.84 Kg/10Sqm.	129.83	Sqm	30.80	
22	Providing and fixing water closer squatting pan (Indian type WC pan) with 100 mm sand cast iron P or S trap level white PVC flushing cistern with manually controlled device (handle lever) comforting to IS :7231 with all fittings and fixtures complete including cutting and making good the walls and floor wherever required white vitreous China Orissa pattern WC pan of size 580X 440mm with flush and integrated type foot rests.	1	each	2304.65	

Remarks : Add 43% for **Ramgarh** under Jharkhand Region approved by CE, CPWD, Patna dated 12.01.2011 due to price escalation. Except Sl. No. 3

Authority of issuing the Tender

212/64

Stamp with Signature.

1. Name of Firms.
2. Address.
3. PAN No.
4. Registration No.
5. Earnest Money.
D.D. No. & Date

Signature of Tendered

GENERAL CONDITION FOR CONTRACT :

1. Work should be done satisfactory as per specification & direction of Engineer in charge.
2. Payment should be made after submission of bill in triplicate after completion of work satisfactory through A/C payee Cheque / DD.
3. No extra taxes will be paid.
4. 5% performance guaranty should be deposited before commencement of work.
5. A security deposit @ 5% , Income tax @ 2% and Cont. Tax as per rule of the total value of work will be deducted from the final bill.


(RAM NATH YADAV)
Executive Engineer