



भारत सरकार
GOVERNMENT OF INDIA
केन्द्रीय जल आयोग
CENTRAL WATER COMMISSION
माही मंडल
MAHI DIVISION

तीसरी मंजिल,
3rd Floor,
नर्मदा तापी भवन
Narmada Tapi Bhawan
सेक्टर 10- ए Sector 10-'A'
गांधीनगर 342010
Gandhinagar-342010
दूरभाषन 0 079 23239509
Tele Fax No.079-23239509
Email: mahi_cwc@yahoo.co.in

पत्र सं : ममं/09W/04/10/HQ-MD/

दिनांक :

कोटेशन आमंत्रण सूचना
Notice Inviting Quotation

Sealed quotations are reinvited for following work on behalf of president of India by this office from the reputed Firms /contractors as per details, terms and conditions given below. The quotation should reach this office latest by 15.00 hours on or before 09.01.12 and the same will be opened on the same day at 15.30 hours in presence of the bidders or representative thereof, if any.

| क्रमांक Sr.No. | कार्यका नाम Description of work | मात्रा Qty | यूनिट Unit | कुल रकम Amount |
|-------------------|---|------------|---------------|-------------------|
| 1 | Construction of Gate pillars with fencing & temporary shed at Sapawada. | 1 | No. | |

Terms and Conditions:-

1. The sealed cover should be Super scribed with words “**Quotation for Construction of Gate pillars with fencing & temporary shed at Sapawada & Date of Opening 09.01.12**”.
2. The bidders should submit quotation with their rates on the blank spaces provided in the NIQ alongwith their letter pads if any and should sign the NIQ with stamp accepting terms & conditions. The quotation in any other form may likely to be rejected.
3. The rates quoted shall be and inclusive of all the duties/ taxes and sales tax/VAT, Octroi if any should be quoted separately.
4. The quoted rates should remain valid for 180 days from the date of opening of the quotations.
5. Quotations erased and over written will be summarily rejected unless corrections are authenticated with bidder's signature.
6. The work should be completed within 30 days of the issue of confirm order.
7. The work should be of good quality and free from defect and if found not suitable the same should be replaced by the contractors at his own cost & risk.
8. The quantity will be decreased or increased at the time of work order for which the contractor should bind to execute the works.

9. The materials should be of good quality and free from defect and if found not suitable the same should be replaced by the contractor at his own cost & risk.
10. The detailed drawings / document can be seen from the office of the undersigned between 14.00 Hrs to 17.00 Hrs. on any working days except Sunday & holidays.
11. The department will not be responsible for any injury sustained to the workers during the performance of their duties on the work and also department will have no obligation to workers for any damage or compensation due to any disputes between the Contractor and the workers.
12. Canvassing in any form whether directly or indirectly is strictly prohibited.
13. In case of any disputes arises, the decision of the undersigned is final and the Contractor will be binded for it.
14. The information of Unsuccessful quotations will not be given to concerned bidders and bidders shall have no claim of any nature on this office.
15. In case of any litigation due to accident, the contractor shall handle at its own cost and in the event of the department happens to be incurred any expenditure towards litigation, the same shall be recovered from the contractor. In case of any dispute, the decision of the "Undersigned" will be final and binding.
16. The "contractor" shall work under the control of the "Undersigned" or his authorized representative.
17. Contractor shall be responsible for the conduct, behaviour and fidelity of the persons employed for the work.
18. Any person of contractor is found in drunken state or found misbehaving while on work or unfit for work; such personnel shall be replaced immediately at the absolute discretion of "Undersigned" or his representative.
19. Payments will be made by A/C payee Cheque payable at SBI, Gandhinagar after completion of satisfactory work, for which a pre-receipted bill in triplicate should be submitted after completion of work. No advance payment shall be made. However, gross work done of Rs 1 lakh (Rs one lakh only) will be eligible for interim payment.
20. Income tax @ 2% of the total value of work will be deducted from the bill.
21. For any breach of conditions mentioned above, the "Undersigned" shall have absolute power to with hold such amount from the claim of the "contractor", which he finds suitable to compensate damages/risk caused by negligence of its personnel.
22. **The offer shall be accompanied with Bid Security of Rs 3000.00 (Rs Three thousand only) in the form of an Account Payee D.D. /Fixed Deposit Receipt/Banker's Cheque from any of the scheduled bank guaranteed by reserve Bank of India in favour of Executive Engineer, Mahi Division, CWC, payable at Gandhinagar or by cash with the cashier of this office.** This should remain valid upto 60 days from the date of opening for acceptance of the quotation. For unsuccessful quotations bid security shall be refunded immediately. **In case of non submission of Bid security, the offer will be liable for rejection.**
23. Bid security shall be forfeited, if successful bidder with-draws his offer before the expiry of the validity period or fails to furnish the performance guarantee / complete the work within the stipulated period from the date of order.
24. **Performance Guarantee will be submitted by successful bidder for 5% value of the contract price** claimed by the "Contractor" to cover the standards of performance. The performance Guarantee for 5% value may be furnished in the form of A/c payee demand draft, FDR and Bank guarantee from of a scheduled bank guaranteed by Reserve Bank of India in favour of the Ex. Engineer, Mahi Division, CWC, Gandhinagar

(Gujarat) payable at State Bank of India, Gandhinagar Branch, Gandhinagar or by cash with the cashier of this office. The Performance Guarantee shall be refunded to the contractor soon after completion of the work and recording of the completion certificate.

25. **Security deposit @ 5% of the gross amount of bill shall be deducted** from the bill of the Contractor. However, the Contractor may deposit the amount of security at the rate mentioned in cash or govt. securities or FDR etc. The above "Security deposit" shall be refunded after completion of all guarantee / warranty obligation.
26. **The whole work shall be guaranteed for a period of 6 (six) months from the date of actual completion as recorded.** The work should be completed satisfactory and in all respect as directed by this office. In the event of any defect is found within the guaranteed period due to faulty design or bad workmanship, the whole work or a part will be replaced by the "Contractor" at site free of cost within 10 days of intimation.
27. Any other rules & codes of CPWD and its amendment as applicable will be binding on the successful bidder for this deal.

[वाई.एस.वाण्णैय]
अधिशसी अभियन्ता

सेवा में

प्रतिलिपि :

- 1 अधीक्षण अभियन्ता [समन्वय] नर्मदा तापी बेसिन संगठन केन्द्रीय जल आयोग गॉधीनगर/ The Superintending Engineer (C), NTBO,CWC, Gandhinagar.
- 2 अधीक्षण अभियन्ता जल वैज्ञानिक प्रेषण परिमण्डल केन्द्रीय जल आयोग गॉधीनगर / The Superintending Engineer, H.O.Circle ,CWC, Gandhinagar
- 3 निदेशक केन्द्रीय जल आयोग एस एम डी बी नई दिल्लीइस निवेदन के साथ भेजा जाता है कि यह वेब साईट पर डिस्पले करवाया जाय | / The Director, CWC, SMDB, New Delhi with request to display on the CWC web site
- 4 अधिशसी अभियन्ता तापी मण्डल केन्द्रीय जल आयोग सूरत / Executive Engineer, Tapi Division, CWC, Surat

- 5 लेखा शाखा माही मण्डल केन्द्रीय जल आयोग गॉधीनगर / Accounts Branch, Mahi Division, CWC, Gandhinagar
- 6 सूचना फलक माही मण्डल केन्द्रीय जल आयोग गॉधीनगर/ Notice Board, Mahi Division, CWC, Gandhinagar
- 7 उपमण्डलीय अभियन्ता सावरमती उप मण्डल/ माही उप मण्डल/उत्तर पश्चिमी नदियों उप मण्डल / बनास लूनी उप मण्डल केन्द्रीय जल आयोग अहमदाबाद/ कडाना/ हिम्मतनगर/ पालनपुर/ SDE , SSD/MSD/NWRSD/BLSD, ahmedabad Kadana/ Himmatnagar/ Palanpur for circulation to Local Agencies.

Name of Work: Construction of Gate pillars with fencing & temp. shed at SAPAWADA

| Sl. No | Description | Unit | Qty. | Rate | Amount in rupees |
|---------------|---|-------------|-------------|-------------|-------------------------|
| 1 | Cleaning and dressing of site including removing of bushes small tree and boulders | Sqm | 930.00 | | |
| 2 | Filling of any kind of soil in area including levelling and dressing etc. | Cum | 550.00 | | |
| 3 | Excavation for foundation upto 1.5m depth including sorting out and stacking of useful materials and disposing of the excavated stuff up to 50m lead | Cum | 0.43 | | |
| 4 | Providing and laying cement concrete 1:3:6 (1. cement: 3 Coarse sand : 6 hand broken stone aggregate 40mm nominal size) & curing complete excluding cost of form work in foundation & plinth . | Cum | 0.108 | | |
| 5 | Providing and laying ordinary cement concrete 1:2:4(1 cement 2:sand:4 aggregate 20mm nominal size) & finishing smooth with curing etc. complete including the cost of form work but excluding the cost of reinforcement for RCC work in column having cross sec | Cum | 0.46 | | |
| 6 | Providing H.Y.S.D. bar reinforcement for R.C.C. work including bending, Binding and placing in position complete up to floor two level. | kg | 36.80 | | |
| 7 | Providing 15mm thick cement plaster in single coat on brick/concrete walls for interior plastering up to two level finishing even & smooth in CM 1:4 | Sqm. | 4.38 | | |
| 8 | White washing with lime on all surface(2 coats) to give an even shades including thoroughly brooming the surface to remove all dirt mortar drops and other foreign matter. | Sqm. | 4.38 | | |
| 9 | Providing and fixing double panelled steel Gate with 35mm tubular outer and inside grided with 12mm square rod design as directed by the Engineer In-charge with approx. Wt. 30 Kg per Sq. M including cost of iron primer & painted 2 cost of enamelled glossy paint. Gate size(3.00x 1.50)M | kg | 135.00 | | |
| 10 | Providing and fixing holdfast for gate | Nos. | 4.00 | | |
| 11 | Painting of two coats (excluding priming coat) on new steel and other metal surface with enamel paint, brushing interior to give an even shade including cleaning the surface of all dirt, dust and other foreign matter. | Sqm | 4.50 | | |
| 12 | Providing and fixing 1.2 M. high fencing with 2.0 M long M.S Angle posts 40 MM x 40MM x 6MM and oil painting 3-coats fixed at 2.5 Mt. C/C with five horizontal lines and two diagonal of galvanized steel barbed wire weighting 9.38 Kg per 100Mt ,strained & fixed to posts with G.I. staples including fixing the post in ground with 0.5mX0.5mX0.5m block in c.c1:5:10 complete. | 1 | 119.00 | | |
| 13 | Providing and fixing hooks for fencing | Nos. | 10.00 | | |
| 14 | Providing & Fixing of 1.5 m high M.S. Sign Board (1.6mm thick) of Size 4'x3' with frame angle iron of (30X30X5) mm and 2.0mt long support M.S angle iron (35X35X6) mm fixing in ground with0.5x0.5x0.5mt block in cc 1:3:6 complete including oil painting | No. | 1.00 | | |

Construction of Temporary Shed at Sapawada

| | | | | | |
|---|--|----------------|-------|--|-------|
| 1 | Cleaning and dressing of site including removing of bushes small , tree and boulders | sqm | 18.00 | | |
| 2 | Excavation for foundation upto 1.5m depth including sorting out and stacking of useful materials and disposing of the excavated stuff up to 50m lead in dense & hard soil | Cum | 4.30 | | |
| 3 | Filling foundation and plinth with murrum or selected soil in layers of 20 mm thickness including watering ,ramming, and consolidation etc, complete | Cum | 1.00 | | |
| 4 | Providing and laying ordinary cement concrete 1:2:4(1 cement :2sand:4 aggregate 20mm nominal size) with curing etc complete excluding the cost of formwork | Cum | 1.70 | | |
| 5 | Brick work using common burnt clay building bricks having crushing strength not less than 35 kg per sqm in superstructure up to floor 2 level in cement mortar 1: 6 (1 cement : 6 fine sand) | Cum | 5.60 | | |
| 6 | Providing corrugated asbestos cement 8 mm thick sheet roofing with GI ,J or L hooks ,bolts and nuts 8 mm thick dia GI plain and bitumen washers complete excluding the cost of purlin, rafters and trusses. -- A.C sheet 0.80 mm thick | Sqm | 17.85 | | |
| 7 | Providing 15mm thick cement plaster in single coat on brick/concrete walls for interior plastering up to floor two level finished even & smooth (inside & out side building) in CM 1:6 | Sqm. | 50.00 | | |
| 8 | White washing with lime on all surface (2 coats) to give an even shades including thoroughly brooming the surface to remove all dirt mortar drops and other foreign matter. | Sqm. | 50.00 | | |
| 9 | Fixing kings post, runners, king truss& purlins in position in tubular constructed wall for temp shed etc complete (Materials supplied by Department) including required washers ,nut & bolts etc. | One Job | | | |
| | | | | | Total |

We agree to execute the above works in accordance with the technical specification and terms & conditions as per your NIQ No. मसं /09W/04/10/HQ-MD/ dt for a contract price Rs (Rupees) with in specified period.

Signature of Contractor with stamp