



भारत सरकार
केंद्रीय जल आयोग
दमनगंगा उप मंडल
सिलवासा

GOVERNMENT OF INDIA
CENTRAL WATER COMMISSION
DAMANGANGA SUB DIVISION
SILVASSA

Tele./Fax (0260) 2640204



Opp: Police line, Dadra & Nagar Haveli, (U.T.)

No. DGSD/NIQ-2011/ 331-45

Dated: 03.09.2011

पुनः निविदा आमंत्रण सूचना
RE-NOTICE INVITING QUOTATION

भारत के राष्ट्रपति की ओर से रजिस्टर्ड ठेकेदारों से नानीपलसन में सन्डास तथा स्नान घर के निर्माण हेतु (जो निम्नलिखित निबंधन पूरे करते हो) मुहरबन्द कोटेशन आमंत्रित किए जाते हैं।

Sealed Quotations are invited on behalf of the President of India for Construction of WC and Bath at Nanipalsan from registered contractors of P.W.D. / C.P.W.D. and other local bodies as per details and terms and conditions below:

क्रमांक / S.No	विवरण(कार्यका नाम /Description of Item/work	Estimated cost	Earnest money
	Construction of WC and Bath at Nanipalsan Site" As shown in Annexure-I	Rs.124360/-	Rs.2487/-

निबंधन व शर्तें :

- कार्य के लोक निर्माण विभाग के विनिर्देशों के अनुसार सम्पन्न किया जायेगा।
The work is to be carried out as per CPWD specification
- हस्ताक्षरित व मुहरबंद कोटेशन (जो कोटेशन फार्म में ही भरना चाहिए) इस कार्यालय को दिनांक **14.09.11** सायं **1500** बजे या उससे पूर्व प्राप्त हो जानी चाहिए जो उसी दिन सायं **1530** बजे अद्योहस्ताक्षरी अथवा प्राधिकृत प्रतिनिधि द्वारा सप्लायर्स या उनके प्रतिनिधि (जो उपस्थित रहना चाहें) की उपस्थिति में खोली जाएगी।
The quotation duly filed in enclosed quotation form only signed should reach this office on or before **14.09.11** up to **1500hrs** and will be opened same day at 15.30 hrs. in the presence of the supplier or their authorized representatives whomsoever will remain present at their own cost at the time of opening.
- कोटेशन मोहर बंद लिफाफे में रखी जानी चाहिए तथा लिफाफे पर कार्य "नानीपलसन में सन्डास तथा स्नान घर का निर्माण" का नाम लिखा होना चाहिए।
The sealed cover should be Super scribed with words "**Construction of WC and Bath at Nanipalsan**"
- भारत के राष्ट्रपति की ओर से अद्योहस्ताक्षरी न्यूनतम या किसी अन्य कोटेशन स्वीकार करने के लिए अपने आपको आवद्ध नहीं करते हैं और प्राप्त सभी कोटेशन या किसी भी कोटेशन को बिना कारण बताए अस्वीकार करने का अधिकार सुरक्षित रखते हैं।
On behalf of President of India the undersigned reserves the right to reject any or all the quotations and to alter the quantity without assigning any reasons thereof.
- दर्शाये गये कार्य / शर्तों की मात्रा कायदेश / पूर्ति आदेश के समय घट अथवा बढ़ सकती है ठेकेदार / आपूर्तिकर्ता कथित दर पर निष्पादन हेतु बाध्य होगा।
The quantity will be decreased or increased at the time of supply order for which the agency should bind to supply material
- कोटेशन के रेट 180 दिनों तक विधिमान्य होने चाहिए।
Rates should have a valid period up to 180 days

- 7 कार्य आदेश जारी होने के 60 दिन में कार्य सम्पन्न होना चाहिए।
The work should be completed within 60 days from the date of the issue of work order.
- 8 उक्त कार्य में प्रयुक्त सामान दोष रहित व विनिर्देशों के अनुरूप होना चाहिए अन्यथा कार्य आदेश अस्वीकृत कर दी जाएगा तथा ठेकेदार स्वयं के खर्च से विनिर्दिष्ट सामान उपलब्ध कराने हेतु बाध्य होगा।
The material to be used should be of standard quality and free from defect and if found not suitable the same shall be asked for replacement at the cost and risk of the agency.
- 9 यह कार्यालय असफल कोटेशन की सूचना देने हेतु कोई कार्यवाही नहीं करेगा।
Intimation of unsuccessful tender / quotation will not be given to concerned firms and the tender / quotations shall have no claim of any nature on this office.
- 10 कार्य सम्पादन की सूचना के साथ प्री स्टॉम्प रसीद विल (दो प्रतियों में) भेजना चाहिए तदोपरांत भुगतान खाता चैक अथवा डिमाण्ड ड्राफ्ट द्वारा किया जाएगा।
Pre-stamp receipt bill in duplicate to be submitted after completion of work. Payment will be released through A/C Pay Cheque drawn on SBI Nanpura, Surat for local supplier and D.D. for out side.
- 11 यदि कार्य निष्पादन निबंधन व शर्तों तथा विनिर्देशों के अनुरूप न करने पर ठेकेदार को बैंक लिफ्ट करने हेतु अन्य विभागों व स्वयं के विभाग के अन्य कार्यालयों की अनुशंसा कर सकता है।
In case the firm fails to carried out the work as per the specifications , requirement and terms and conditions after quoting the rates for items the firm will be recommended for black list by various State / Central Govt. departments
- 12 उक्त कार्य के लिए केंद्रीय लोक निर्माण विभाग कोड विनिर्देश तथा अन्य संबन्धित कोड पूर्ति कार्य निष्पादन हेतु पालन बाध्य होगा।
Any other rules of CPWD Codes and its amendment as applicable will be binding on the successful bidder.
- 13 सभी कटिंग ओव्हरसाइटिंग हस्ताक्षरित होना चाहिए।
All cuttings / omissions should be signed.
- 14 सरकारद्वारा निर्धारित टैक्स आदि की कटौती आवश्यकतानुसार कर ली जाएगी।
Taxes as applicable will be deducted at the source from the bill at the time of payment.
- 15 कोटेशन के मामले में किसी भी प्रकार का प्रत्यक्ष या अप्रत्यक्ष प्रेरण पूर्णतया निषिद्ध है।
Convassing whether directly or indirectly is strictly prohibited.
- 16 उक्त कार्य सम्पादन के लिए निर्धारित समय महत्व पूर्ण होगा तथा समय वृद्धि केवल संतोष जनक व अपरिहार्य परिस्थिती में दिया जायेगा।
Time allowed for completion will be essence of quotation. Extension of time will be allowed only after submission of valid reason of delay.
- 17 सिक्योरिटी डिपॉजिट पूरे कार्य की लागत का 10 प्रतिशत विल में से काट लिया जायेगा जो 6 महीने के बाद लौटाया जायेगा।
Security deposit @ 10% of gross amount of work will be deducted from the bill and will be released after completion of 6 months.
- 18 Bid security @ 2% i.e. for Rs. 2487- (Rupees two thousand four hundred eighty seven) only to be submitted along with the quotation by cash or Demand Draft in favour of "EXECUTIVE ENGINEER, TAPI DIVISION, CWC,SURAT" Payable in State Bank India Nanpura Branch at Surat. Quotation without Bid Security will be rejected.

प्रतिलिपि :

- 1। अधीक्षण अभियंता जल वैज्ञानिक प्रेक्षण परिमण्डल केन्द्रीय जल आयोग गाँधीनगर / The Superintending Engineer, H.O.Circle ,CWC, Gandhinagar
- 2। अधीक्षण अभियंता (समन्वय) केन्द्रीय जल आयोग गाँधीनगर The Superintending Engineer (Co-ord) CWC Gandhinagar
- 3। निदेशक केन्द्रीय जल आयोग एस एम डी वी नई दिल्लीइस निवेदन के साथ भेजा जाता है कि यह वेब साईट पर डिस्पले करवाया जाय। / The Director, CWC, SMDB, New Delhi with request to display on the CWC web site.
- 4। अधिशासी अभियंता माही मण्डल केन्द्रीय जल आयोग गाँधीनगर/ Executive Engineer CWC, Mahi Division, Gandhinagar
- 5। अधिशासी अभियंता तापी मण्डल केन्द्रीय जल आयोग सुरत / Executive Engineer CWC, Tapi Division, Surat.
- 6। Sub Divisional Engineer LTSD- Surat/LNSD-Bharuch/MTSD Dhule/UTSD Bhusawal for information please
- 7। लेखा शाखा तापी मण्डल केन्द्रीय जल आयोग सुरत/ Accounts Branch, Tapi Division, CWC, Surat
- 8। सूचना फलक दमनगंगा उपमंडल केन्द्रीय जल आयोग सिलवासा/ Notice Board, DGSD, CWC, Silvassa.

ANNEXURE-1

NAME OF WORK: Construction of W.C. & Bath at Nanipalsan under DGSD, CWC, Silvassa.

Sl. No.	Description	Qty	Rate	Unit	Amount
1	Providing materials and labour for Excavation for foundation up to 1.5 mt. depth including sorting out and stacking of useful materials and disposing of the excavated stuff up to 50 m lead dense or hard soil .	11.69		Cum	
2	Providing material and labour for laying cement concrete 1:4:8 (1 cement : 4 coarse and : 8 stone aggregates 40 mm nominal size) and curing complete including cost of form work in (A) Foundation and Plinth.	3.47		Cum	
3	Providing material and labour for Reinforced cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and curing complete including cost of form work but excluding cost of reinforcement for beam & lintel	0.43		Cum	
4.	Providing brick masonry in cement mortar 1:6 using conventional brick in Foundation & plinth and bailing out water manually striking joints on exposed face raking out joints on exposed face and watering complete.	8.577		Cum	
5.	Providing brick masonry in cement mortar 1:6 using conventional brick in superstructure and bailing out water manually striking joints on exposed face raking out joints on exposed face and watering complete.	6.606		Cum	
6.	Earth filing in plinth and floor with approved excavated materials in 15 to 20 cm layer including watering and compaction complete.	1.987		Cum	
7.	Providing material and labour for T.M.T. Fe. 415 Bar reinforcement for RCC work including, bending, and placing in position complete up to floor to level.	43.0		Kg	
8.	Providing and fixing fabricated steel door as per drawing enclosed with M.S.Angle frame of size 50 x 50 x 5 mm angle frame for door shutter of 40x40x6 mm and with G.I. Sheet or M.S.Sheet of 18 mm gauge with sufficient bracing, flat including providing with all droop, tower bolts, Hinges, handle etc. complete with two coats of primer and two coats of good quality Enameled paint complete as directed.	1.50		Sqm	
9.	Providing and fixing in position Aluminum louvered windows / ventilators of various sizes with powder coating as per detailed drawings and specifications including aluminum frames 80 x 38 mm box type, 5 mm thick sheet glass louvers, clips / rubber plain P.V.C. gaskets of approved quality etc. complete. (Sample to be got approved from Exe. Engineer before use) Spec. No. As directed by Engineer in charge.	0.54		Sqm	
10.	Providing material and labour for 12 mm thick cement plaster (1:3) without neeru finish in single coat for plastering on Brick / concrete wall surface for plastering up to floor to level including scaffolding and curing complete.	68.09		Sqm	
11	Providing neeru finish to plastered surface in all position except ceiling including scaffolding and curing complete.	68.09		Sqm	
12	Providing & fixing M.S. Angle of size 40x40x6mm with applying one coat primer & two coat of good quality enameled paint	35.42		Kg	
13.	Providing & fixing corrugated G. I. sheet 0.80mm thickness (22BWG) for roofing with wind tiles fixed with galvanized iron J or L hook, bolts & nuts 8mm dia with bitumen & G. I. limpetwasher filled with white lead complete excluding the cost of purlin,rafter & trusses (1) 0.8mm thick	12.01		Sqm	
14	Providing and applying washable oil bound distemper of approved colour and shade	68.09		Sqm	

	to old and new surface in two coats including scaffolding,preparing the surface (excluding the primer coat)				
15.	Providing and fixing IOrrisa type water closet CL. GL. 25 inch white glazed earthen were WC pan of approved design and quality without flushing system including fixing in cement motor with pair of glazed foot rest including 'S' trap etc. complete.	1		No	
16	Providing and laying white glazed tiles of 148.5mm x 148.5mm in size and 5.5mm to 6.6mm thick for flooring in required position laid on bed of 1:6 cement mortars including neat cement float filing joints with neat white cement slurry, curing and cleaning complete.	9.90		Sqm	
17.	Providing and fixing chromium plated TOWEL ROD with clamps [16 mm dia] 75cm in length	1		No	
18	Providing and fixing 10 cm x 5cmx30cm C.I. Nahani trap including C.I. grating, bend and piece of C.I. pipe up to the outside face of the Wall complete.	1		No	

FOR SEPTIC TANK & SOAKPIT

Sl. No.	Description	Qty	Rate	Unit	Amount
1	Providing materials and labour are Excavation for foundation up to 3 mt. depth including sorting out and stacking of useful materials and disposing of the excavated stuff up to 50 m lead dense or hard soil .	20.50		Cum	
2	Providing material and labour for laying cement concrete 1:3:6 (1 cement : 3 coarse and : 6 stone aggregates 40 mm nominal size) and curing complete excluding cost of form work in (A) Foundation and Plinth.	1.13		Cum	
3	Providing brick masonry in cement mortar 1:4 using first class brick in foundation and in plinth and bailing out water manually striking joints on exposed face raking out joints on exposed face and watering complete .	3.29		Cum	
4	Providing brick masonry in cement mortar 1:6 using 2 ND class brick in foundation and in plinth and bailing out water manually striking joints on exposed face raking out joints on exposed face and watering complete	0.622		Cum	
5	Providing and laying 2 nd class dry brick work in soak pit.	2.22		Cum	
6	Precost reinforce cement concrete work finished smooth including steel reinforcements complete laid in position	0.394		Cum	
7	12mm cement plaster (1:3) in septic tank	9.86		Sqm	
8	20 mm cement plaster (1:4) with standard water proofing compound in floor of septic tank	1.80		Sqm	
9	50 mm size brick aggregate for soak pit	2.05		Cum	
10	Coarse sand outer side of soak pit	2.25		Cum	
11	Iron foot steps of 16 mm dia. Bar	4		Nos.	
12	100 mm dia. S.W. pipe layng and jointing with 1:3 cement mortar complete.....	4.0		R M	
13	S.W. Tee 100 mm dia. With one leg of 40 cm	1		No.	
14	S.W. Bend 100 mm dia	1		No.	
15	100mm dia PVC ventilating pipe and rain water pipe	10		R.M.	
16	100 mm dia PVC cowl at top of ventilating pipe	2		No.	