

GOVERNMENT OF INDIA  
CENTRAL WATER COMMISSION  
OFFICE OF THE EXECUTIVE ENGINEER  
DAMODAR DIVISION, APCAR GARDEN (WEST)  
ASANSOL-713304

No. DD/DB/Tender/2011-12 /1648-59

dated :- 25 / 07/2011

**NOTICE INVITING TENDER**

On behalf of The President of India, the under signed invites Sealed tender from the reputed /registered experienced agency for the following work. Contractor are requested to submit their tenders in the official tender box or through registered post upto 1500 hrs on 18/08/2011

S.No	Description of work	Estimated Amount	Earnest Money (refundable)	Cost of Tender in Rs.	Period of contract
<b>Construction of Cabin at Sites</b>					
1	Tilaiya	Rs. 1,55,160/-	Rs. 3,110/-	Rs. 500/- in cash	90(Ninety) days
2	Pupanki	Rs. 1,55,160/-	Rs. 3,110/-	-do-	- do -
3	Nandadih	Rs. 1,55,160/-	Rs. 3,110/-	-do-	- do -
4	Tantloi	Rs. 1,55,160/-	Rs. 3,110/-	-do-	- do -
5	Maharo	Rs. 1,55,160/-	Rs. 3,110/-	-do-	- do -
6	Messanjore	Rs. 1,55,160/-	Rs. 3,110/-	-do-	- do -
7	Tilpara Barrage	Rs. 1,57,330/-	Rs. 3150/-	-do-	- do -
8	Jamalpur	Rs. 1,75,770/-	Rs. 3520/-	-do-	- do -

The above tender will be opened at 15.30 Hrs. on the same day. Earnest money in favour of Executive Engineer, Damodar Division, Central Water Commission, Asansol as prescribed in the tender documents should be deposited with the tender in the Form of D.C.R. issued from any nationalized bank/ cash. The tender of the agency who do not deposit earnest money in the prescribed manner are liable to be rejected.

A complete set of tender document of the above work containing detailed terms and conditions, Schedule of quantity can be obtained by the eligible agencies from the office of the undersigned up to 1600 Hrs. on 17/08/2011 on all working days between 11.00 A.M. to 4.00 P.M. on submission of written application up to 16.00 Hrs. on 16/08/2011.

In case of above date of receiving and opening date of tender is declared holiday etc. the tender shall be received & opened on the next working day as per schedule time. More details are available on web site [cwc-tender@mail.nic.in](mailto:cwc-tender@mail.nic.in) & [smdte@nic.in](mailto:smdte@nic.in).

( RAM NATH YADAV )  
EXECUTIVE ENGINEER

Contd. ... 2

Copy along with enclose forwarded for information with request for board publicity through pasting on his office Notice board:-

1. The Director, SMD, CWC, New Delhi is requested to get published in CWC web site. Email for this purpose has already been sent.
2. The SE, HOC, CWC, Maithon Dam ( Jharkhand).
3. The E.E. Lower Ganga Division, CWC, Berhampore.
4. The S.D.E, Tenughat/Maithon/Midnapore/Suri/Durgapur/ Kolkata
5. The A.D. II, Head Quarter, Damodar Division, CWC, Asansol.
6. The AAO, A / B, Damodar Division, CWC, Asansol.
7. Notice Board, Damodar Division, CWC, Asansol

( RAM NATH YADAV )  
EXECUTIVE ENGINEER

## ANNEXTURE – I

### DETAILS

1	Name of work	Construction of Cabin
2	Estimated Amount	:-Rs. 1,55,160/-(Rupees One lakh fifty five thousand one hundred sixty) only for SL.No 1 to 6, Rs. 1,57,330/-(Rupees One lakh fifty seven thousand three hundred thirty) only for SL. No. 7 and Rs. 1,75,770/-(Rupees One lakh seventy five thousand seven hundred seventy) only for Sl.No. 8.
3	Cost of tender Document	:-Rs. 500/- ( Rupees five hundred) only
4	Earnest Money	:-Rs. 3,110/--(Rupees three thousand one hundred ten ) only for SL.No 1 to 6, Rs. 3150/- for SL. No. 7 and Rs. 3520/- for Sl.No. 8.
5	Security Deposit	:- 05 % of the gross value of work shall be deducted from the final bill.
6	Performance Guarantee	:- 5 % on the work order amount shall be deposited before commencement of work
7	Time completion of work	:- 90 (Ninety) days from 7 <sup>th</sup> date of issue of work order
8	Last date of receipt of application for issue of tender	:- 16/08/.2011 upto 16.00 Hrs
9	Last date of sale of tender	:- Up to 16.00 Hrs. on 17/08/.2011
10	Last date of receiving of tender	:- Upto 15.00 on 18/08/.2011
11	Date of opening tender	:- On 18/08/.2011 at 15.30 hrs. ( if the opening date of tender happens to be a holiday under any circumstance the tender will be opened on the next working day at the same time)
12	Contractor can visit the working site before quoting rates for tender to assess the quantum of work if required	

EXECUTIVE ENGINEER

TENDER10-11.doc

## SCHEDULE

### Name of work :- **Constructioun of Cabin**

Sl. No	Sub- head and item of work	Qty.	Unit	Tilaiya	
				Rate supplied	quoted by agency
1	Earth work in excavation manually in foundation trenches ( not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil.	10.06	Cum	103.40	
2	Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete.	1.23	Cum	301.50	
3	Brick Soling with Jhama brick/ khoa of 15 cm rammed to 10 cm including watering as per direction of Engineer in charge.	1.23	Cum	3000.00	
4	Providing and laying position cement concrete of specified grade excluding the cost of centering and shuttering – all work upto plinth 1:2:4 cement mortar.	1.63	Cum	3149.10	
5	1:2:4 PCC work of specified grade excluding the cost of centering and shuttering. All works in foundation up to plinth level.	6.14	Cum	2121.75	
6	Filling available excavated earth ( excluding rock) in trenches, plinth, sides of foundation , etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m.	2.74	Cum	45.70	
7	Providing and laying damp proof course 40mm thick with Cement concrete 1:2:4	3.38	Sqm	144.15	
8	Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6.	13.14	Cum	2430.30	
9	Reinforcement cement concrete work in beams suspended floors, roofs having slope up to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.	3.15	Cum	3673.85	
10	Reinforcement for RCC work including strightning,cutting,bending, placing in position and binding all complete.Mild steel and Medium Tensile steel bars.	380	Kg	41.50	
11	Centering and shuttering including strutting proping etc.and removal of suspended floors, roofs, landing balconies and access platform.	16.70	Sqm	187.35	
12	Centering and shuttering including strutting proping etc.and removal of lintels, beams, plinth beams and cantilevers.	11.92	Sqm	162.65	
13	Cement concrete flooring 1:2:4 finishing sluary, but excluding the cost of nosing of steps etc. complete.	15.00	Sqm	192.95	
14	Cement plaster (in fine sand) 20mm thick cement plaster of mix 1:6.	65.08	Sqm	95.10	
15	Cement plaster (in fine sand) 12 thick cement plaster of mix 1:6.	67.65	Sqm	67.65	

Sl. No	Sub- head and item of work	Qty.	Unit	Tilaiya	
				Rate supplied	quoted by agency
16	Cement plaster skirting ( upto 30cm) with cement mortar 1:3 finished with a floating coat of neat cement 18mm thick.	11.42	Sqm	168.50	
17	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade on new work ( two/ more coats) over & including priming coat with cement primer.	65.08	Sqm	41.55	
18	Finishing wall with water proofing cement paint of required shed new work ( two or more ) coats applied @ 3.84 Kg/10Sqm.	66.79	Sqm	30.80	

Remarks : Add 43% for Tilaiya under Jharkhand Region approved by CE, CPWD, Patna dated 12.01.2011 due to price escalation.

Authority of issuing the Tender

**Stamp with Signature.**

## SCHEDULE

### Name of work :- **Construction of Cabin**

Sl. No	Sub- head and item of work	Qty.	Unit	Pupanki	
				Rate supplied	quoted by agency
1	Earth work in excavation manually in foundation trenches ( not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil.	10.06	Cum	103.40	
2	Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete.	1.23	Cum	301.50	
3	Brick Soling with Jhama brick/ khoa of 15 cm rammed to 10 cm including watering as per direction of Engineer in charge.	1.23	Cum	3000.00	
4	Providing and laying position cement concrete of specified grade excluding the cost of centering and shuttering – all work upto plinth 1:2:4 cement mortar.	1.63	Cum	3149.10	
5	1:2:4 PCC work of specified grade excluding the cost of centering and shuttering. All works in foundation up to plinth level.	6.14	Cum	2121.75	
6	Filling available excavated earth ( excluding rock) in trenches, plinth, sides of foundation , etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m.	2.74	Cum	45.70	
7	Providing and laying damp proof course 40mm thick with Cement concrete 1:2:4	3.38	Sqm	144.15	
8	Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6.	13.14	Cum	2430.30	
9	Reinforcement cement concrete work in beams suspended floors, roofs having slope up to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.	3.15	Cum	3673.85	
10	Reinforcement for RCC work including strightning,cutting,bending, placing in position and binding all complete.Mild steel and Medium Tensile steel bars.	380	Kg	41.50	
11	Centering and shuttering including strutting proping etc.and removal of suspended floors, roofs, landing balconies and access platform.	16.70	Sqm	187.35	
12	Centering and shuttering including strutting proping etc.and removal of lintels, beams, plinth beams and cantilevers.	11.92	Sqm	162.65	
13	Cement concrete flooring 1:2:4 finishing sluary, but excluding the cost of nosing of steps etc. complete.	15.00	Sqm	192.95	
14	Cement plaster (in fine sand) 20mm thick cement plaster of mix 1:6.	65.08	Sqm	95.10	
15	Cement plaster (in fine sand) 12 thick cement plaster of mix 1:6.	67.65	Sqm	67.65	

Sl. No	Sub- head and item of work	Qty.	Unit	Pupanki	
				Rate supplied	quoted by agency
16	Cement plaster skirting ( upto 30cm) with cement mortar 1:3 finished with a floating coat of neat cement 18mm thick.	11.42	Sqm	168.50	
17	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade on new work ( two/ more coats) over & including priming coat with cement primer.	65.08	Sqm	41.55	
18	Finishing wall with water proofing cement paint of required shed new work ( two or more ) coats applied @ 3.84 Kg/10Sqm.	66.79	Sqm	30.80	

Remarks : Add 43% for Pupanki under Jharkhand Region approved by CE, CPWD, Patna dated 12.01.2011 due to price escalation.

Authority of issuing the Tender

**Stamp with Signature.**

## SCHEDULE

### Name of work :- **Constructiuon of Cabin**

Sl. No	Sub- head and item of work	Qty.	Unit	Nandadih	
				Rate supplied	quoted by agency
1	Earth work in excavation manually in foundation trenches ( not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil.	10.06	Cum	103.40	
2	Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete.	1.23	Cum	301.50	
3	Brick Soling with Jhama brick/ khoa of 15 cm rammed to 10 cm including watering as per direction of Engineer in charge.	1.23	Cum	3000.00	
4	Providing and laying position cement concrete of specified grade excluding the cost of centering and shuttering – all work upto plinth 1:2:4 cement mortar.	1.63	Cum	3149.10	
5	1:2:4 PCC work of specified grade excluding the cost of centering and shuttering. All works in foundation up to plinth level.	6.14	Cum	2121.75	
6	Filling available excavated earth ( excluding rock) in trenches, plinth, sides of foundation , etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m.	2.74	Cum	45.70	
7	Providing and laying damp proof course 40mm thick with Cement concrete 1:2:4	3.38	Sqm	144.15	
8	Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6.	13.14	Cum	2430.30	
9	Reinforcement cement concrete work in beams suspended floors, roofs having slope up to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.	3.15	Cum	3673.85	
10	Reinforcement for RCC work including strightning,cutting,bending, placing in position and binding all complete.Mild steel and Medium Tensile steel bars.	380	Kg	41.50	
11	Centering and shuttering including strutting proping etc.and removal of suspended floors, roofs, landing balconies and access platform.	16.70	Sqm	187.35	
12	Centering and shuttering including strutting proping etc.and removal of lintels, beams, plinth beams and cantilevers.	11.92	Sqm	162.65	
13	Cement concrete flooring 1:2:4 finishing sluary, but excluding the cost of nosing of steps etc. complete.	15.00	Sqm	192.95	
14	Cement plaster (in fine sand) 20mm thick cement plaster of mix 1:6.	65.08	Sqm	95.10	
15	Cement plaster (in fine sand) 12 thick cement plaster of mix 1:6.	67.65	Sqm	67.65	

Sl. No	Sub- head and item of work	Qty.	Unit	Nandadih	
				Rate supplied	quoted by agency
16	Cement plaster skirting ( upto 30cm) with cement mortar 1:3 finished with a floating coat of neat cement 18mm thick.	11.42	Sqm	168.50	
17	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade on new work ( two/ more coats) over & including priming coat with cement primer.	65.08	Sqm	41.55	
18	Finishing wall with water proofing cement paint of required shed new work ( two or more ) coats applied @ 3.84 Kg/10Sqm.	66.79	Sqm	30.80	

Remarks : Add 43% for Nandadih under Jharkhand Region approved by CE, CPWD, Patna dated 12.01.2011 due to price escalation.

Authority of issuing the Tender

**Stamp with Signature.**

## SCHEDULE

### Name of work :- **Constructiuon of Cabin**

Sl. No	Sub- head and item of work	Qty.	Unit	Tantloi	
				Rate supplied	quoted by agency
1	Earth work in excavation manually in foundation trenches ( not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil.	10.06	Cum	103.40	
2	Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete.	1.23	Cum	301.50	
3	Brick Soling with Jhama brick/ khoa of 15 cm rammed to 10 cm including watering as per direction of Engineer in charge.	1.23	Cum	3000.00	
4	Providing and laying position cement concrete of specified grade excluding the cost of centering and shuttering – all work upto plinth 1:2:4 cement mortar.	1.63	Cum	3149.10	
5	1:2:4 PCC work of specified grade excluding the cost of centering and shuttering. All works in foundation up to plinth level.	6.14	Cum	2121.75	
6	Filling available excavated earth ( excluding rock) in trenches, plinth, sides of foundation , etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m.	2.74	Cum	45.70	
7	Providing and laying damp proof course 40mm thick with Cement concrete 1:2:4	3.38	Sqm	144.15	
8	Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6.	13.14	Cum	2430.30	
9	Reinforcement cement concrete work in beams suspended floors, roofs having slope up to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.	3.15	Cum	3673.85	
10	Reinforcement for RCC work including strightning,cutting,bending, placing in position and binding all complete.Mild steel and Medium Tensile steel bars.	380	Kg	41.50	
11	Centering and shuttering including strutting proping etc.and removal of suspended floors, roofs, landing balconies and access platform.	16.70	Sqm	187.35	
12	Centering and shuttering including strutting proping etc.and removal of lintels, beams, plinth beams and cantilevers.	11.92	Sqm	162.65	
13	Cement concrete flooring 1:2:4 finishing sluary, but excluding the cost of nosing of steps etc. complete.	15.00	Sqm	192.95	
14	Cement plaster (in fine sand) 20mm thick cement plaster of mix 1:6.	65.08	Sqm	95.10	
15	Cement plaster (in fine sand) 12 thick cement plaster of mix 1:6.	67.65	Sqm	67.65	

Sl. No	Sub- head and item of work	Qty.	Unit	Tantloi	
				Rate supplied	quoted by agency
16	Cement plaster skirting ( upto 30cm) with cement mortar 1:3 finished with a floating coat of neat cement 18mm thick.	11.42	Sqm	168.50	
17	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on new work ( two/ more coats) over & including priming coat with cement primer.	65.08	Sqm	41.55	
18	Finishing wall with water proofing cement paint of required shed new work ( two or more ) coats applied @ 3.84 Kg/10Sqm.	66.79	Sqm	30.80	

Remarks : Add 43% for Tantloi under Jharkhand Region approved by CE, CPWD, Patna dated 12.01.2011 due to price escalation.

Authority of issuing the Tender

**Stamp with Signature.**

## **SCHEDULE**

### **Name of work :- Constructiuon of Cabin**

Sl. No	Sub- head and item of work	Qty.	Unit	Maharo	
				Rate supplied	quoted by agency
1	Earth work in excavation manually in foundation trenches ( not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil.	10.06	Cum	103.40	
2	Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete.	1.23	Cum	301.50	
3	Brick Soling with Jhama brick/ khoa of 15 cm rammed to 10 cm including watering as per direction of Engineer in charge.	1.23	Cum	3000.00	
4	Providing and laying position cement concrete of specified grade excluding the cost of centering and shuttering – all work upto plinth 1:2:4 cement mortar.	1.63	Cum	3149.10	
5	1:2:4 PCC work of specified grade excluding the cost of centering and shuttering. All works in foundation up to plinth level.	6.14	Cum	2121.75	
6	Filling available excavated earth ( excluding rock) in trenches, plinth, sides of foundation , etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m.	2.74	Cum	45.70	
7	Providing and laying damp proof course 40mm thick with Cement concrete 1:2:4	3.38	Sqm	144.15	
8	Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6.	13.14	Cum	2430.30	
9	Reinforcement cement concrete work in beams suspended floors, roofs having slope up to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.	3.15	Cum	3673.85	
10	Reinforcement for RCC work including strightning,cutting,bending, placing in position and binding all complete.Mild steel and Medium Tensile steel bars.	380	Kg	41.50	
11	Centering and shuttering including strutting proping etc.and removal of suspended floors, roofs, landing balconies and access platform.	16.70	Sqm	187.35	
12	Centering and shuttering including strutting proping etc.and removal of lintels, beams, plinth beams and cantilevers.	11.92	Sqm	162.65	
13	Cement concrete flooring 1:2:4 finishing sluary, but excluding the cost of nosing of steps etc. complete.	15.00	Sqm	192.95	
14	Cement plaster (in fine sand) 20mm thick cement plaster of mix 1:6.	65.08	Sqm	95.10	
15	Cement plaster (in fine sand) 12 thick cement plaster of mix 1:6.	67.65	Sqm	67.65	

Sl. No	Sub- head and item of work	Qty.	Unit	Maharo	
				Rate supplied	quoted by agency
16	Cement plaster skirting ( upto 30cm) with cement mortar 1:3 finished with a floating coat of neat cement 18mm thick.	11.42	Sqm	168.50	
17	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on new work ( two/ more coats) over & including priming coat with cement primer.	65.08	Sqm	41.55	
18	Finishing wall with water proofing cement paint of required shed new work ( two or more ) coats applied @ 3.84 Kg/10Sqm.	66.79	Sqm	30.80	

Remarks : Add 43% for Maharo under Jharkhand Region approved by CE, CPWD, Patna dated 12.01.2011 due to price escalation.

Authority of issuing the Tender

**Stamp with Signature.**

## SCHEDULE

### Name of work :- **Construction of Cabin**

Sl. No	Sub- head and item of work	Qty.	Unit	Messanjore	
				Rate supplied	quoted by agency
1	Earth work in excavation manually in foundation trenches ( not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil.	10.06	Cum	103.40	
2	Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete.	1.23	Cum	301.50	
3	Brick Soling with Jhama brick/ khoa of 15 cm rammed to 10 cm including watering as per direction of Engineer in charge.	1.23	Cum	3000.00	
4	Providing and laying position cement concrete of specified grade excluding the cost of centering and shuttering – all work upto plinth 1:2:4 cement mortar.	1.63	Cum	3149.10	
5	1:2:4 PCC work of specified grade excluding the cost of centering and shuttering. All works in foundation up to plinth level.	6.14	Cum	2121.75	
6	Filling available excavated earth ( excluding rock) in trenches, plinth, sides of foundation , etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m.	2.74	Cum	45.70	
7	Providing and laying damp proof course 40mm thick with Cement concrete 1:2:4	3.38	Sqm	144.15	
8	Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6.	13.14	Cum	2430.30	
9	Reinforcement cement concrete work in beams suspended floors, roofs having slope up to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.	3.15	Cum	3673.85	
10	Reinforcement for RCC work including strightning,cutting,bending, placing in position and binding all complete.Mild steel and Medium Tensile steel bars.	380	Kg	41.50	
11	Centering and shuttering including strutting proping etc.and removal of suspended floors, roofs, landing balconies and access platform.	16.70	Sqm	187.35	
12	Centering and shuttering including strutting proping etc.and removal of lintels, beams, plinth beams and cantilevers.	11.92	Sqm	162.65	
13	Cement concrete flooring 1:2:4 finishing sluary, but excluding the cost of nosing of steps etc. complete.	15.00	Sqm	192.95	
14	Cement plaster (in fine sand) 20mm thick cement plaster of mix 1:6.	65.08	Sqm	95.10	
15	Cement plaster (in fine sand) 12 thick cement plaster of mix 1:6.	67.65	Sqm	67.65	

Sl. No	Sub- head and item of work	Qty.	Unit	Messanjore
--------	----------------------------	------	------	------------

quoted by agency • • 16 • Cement plaster skirting ( upto 30cm) with cement mortar 1:3 finished with a floating coat of neat cement 18mm thick. •

11.42 •

Sqm •

168.50 • • • 17 • Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on new work ( two/ more coats) over & including priming coat with cement primer. •

65.08 •

Sqm •

41.55 • • • 18 • Finishing wall with water proofing cement paint of required shed new work ( two or more ) coats applied @ 3.84 Kg/10Sqm. •

66.79 •

Sqm •

30.80 • • •

Remarks : Add 43% for Messanjore under Jharkhand Region approved by CE, CPWD, Patna dated 12.01.2011 due to price escalation.

Authority of issuing the Tender

Stamp with Signature.

## SCHEDULE

### Name of work :- **Constructioun of Cabin**

Sl.

No•Sub- head and item of work•Qty. •Unit•**Tilpara Barrage**•••••Rate supplied•quoted by agency••

1• Earth work in excavation manually in foundation trenches ( not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil.●

10.06●

Cum●

103.40●••• 2• Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete. ●

1.23●

Cum●

301.50●••• 3• Brick Soling with Jhama brick/ khoa of 15 cm rammed to 10 cm including watering as per direction of Engineer in charge. ●

1.23●

Cum●

3000.00●••• 4• Providing and laying position cement concrete of specified grade excluding the cost of centering and shuttering – all work upto plinth 1:2:4 cement mortar.●

1.63●

Cum●

3149.10●••• 5• 1:2:4 PCC work of specified grade excluding the cost of centering and shuttering. All works in foundation up to plinth level.●

6.14●

Cum●

2121.75●••• 6• Filling available excavated earth ( excluding rock) in trenches, plinth, sides of foundation , etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m. ●

2.74●

Cum●

45.70●••• 7• Providing and laying damp proof course 40mm thick with Cement concrete 1:2:4●

3.38●

Sqm●

144.15●••• 8• Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6.●

13.14●

Cum●

2430.30●••• 9• Reinforcement cement concrete work in beams suspended floors, roofs having slope up to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.●

3.15●

Cum●

3673.85●••• 10• Reinforcement for RCC work including strightning,cutting,bending, placing in position and binding all complete.Mild steel and Medium Tensile steel bars. ●

380●

Kg●

41.50●••• 11• Centering and shuttering including strutting proping etc.and removal of suspended floors, roofs, landing balconies and access platform. ●

16.70●

Sqm●

187.35●••• 12• Centering and shuttering including strutting proping etc.and removal of lintels, beams, plinth beams and cantilevers.●

11.92●

162.65	Sqm
etc. complete.	
	15.00
	Sqm
192.95	
	65.08
	Sqm
95.10	
	67.65
	Sqm
67.65	
	2
Sl.	
No	
agency	
of neat cement 18mm thick.	
	11.42
	Sqm
168.50	
to give an even shade on new work ( two/ more coats) over & including priming coat with cement primer.	
	65.08
	Sqm
41.55	
coats applied @ 3.84 Kg/10Sqm.	
	66.79
	Sqm
30.80	
Remarks : Add 45% for Tilpara Barrage under Bolpur / Suri Region approved by CE, CPWD, Kolkata Kolkata dated 27.01.2011 due to price escalation.	

Authority of issuing the Tender

**Stamp with Signature.**

## SCHEDULE

### **Name of work :- Constructioun of Cabin**

Sl.

No

work in excavation manually in foundation trenches ( not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil.

10.06  
Cum

103.40

watering, ramming, consolidating and dressing complete.

1.23  
Cum

301.50

direction of Engineer in charge.

1.23  
Cum

3000.00

centering and shuttering – all work upto plinth 1:2:4 cement mortar.

1.63  
Cum

3149.10

works in foundation up to plinth level.

6.14  
Cum

2121.75

, etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m.

2.74  
Cum

45.70

3.38  
Sqm

144.15

shapes and size in cement mortar 1:6.

13.14  
Cum

2430.30

to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.

3.15  
Cum

3673.85

and binding all complete. Mild steel and Medium Tensile steel bars. •

380•  
Kg•

41.50••• 11• Centering and shuttering including strutting propping etc. and removal of suspended floors, roofs, landing balconies and access platform. •

16.70•  
Sqm•

187.35••• 12• Centering and shuttering including strutting propping etc. and removal of lintels, beams, plinth beams and cantilevers. •

11.92•  
Sqm•

162.65••• 13• Cement concrete flooring 1:2:4 finishing sluary, but excluding the cost of nosing of steps etc. complete. •

15.00•  
Sqm•

192.95••• 14• Cement plaster (in fine sand) 20mm thick cement plaster of mix 1:6. •

65.08•  
Sqm•

95.10••• 15• Cement plaster (in fine sand) 12 thick cement plaster of mix 1:6. •

67.65•  
Sqm•

67.65•••

2

Sl.

No• Sub- head and item of work• Qty. • Unit• **Jamalpur**••••• Rate supplied• quoted by agency•• 16• Cement plaster skirting ( upto 30cm) with cement mortar 1:3 finished with a floating coat of neat cement 18mm thick. •

11.42•  
Sqm•

168.50••• 17• Distemping with oil bound washable distemper of approved brand and manufacture to to give an even shade on new work ( two/ more coats) over & including priming coat with cement primer. •

65.08•  
Sqm•

41.55••• 18• Finishing wall with water proofing cement paint of required shed new work ( two or more ) coats applied @ 3.84 Kg/10Sqm. •

66.79•  
Sqm•

30.80•••

Remarks : Add 45% for Jamalpur under West Midnapore Region approved by CE, CPWD, Kolkata Kolkata dated 27.01.2011 due to price escalation.

Authority of issuing the Tender

**Stamp with Signature.**

Name of Firms.

Address.

PAN No.

Registration No.

Earnest Money.

D.D. No. & Date

**Signature of Tendered**

**GENERAL CONDITION FOR CONTRACT :**

1. Work should be done satisfactory as per specification & direction of Engineer in charge.

Payment should be made after submission of bill in triplicate after completion satisfactory through A/C payee Cheque / DD.

No extra taxes will be paid.

5% performance guaranty should be deposited before commencement of

A security deposit @ 5% , Income tax @ 2% and Cont. Tax as per rule of the value of work will be deducted from the final bill.

**( RAM NATH YADAV )  
Executive Engineer**

Phone no. 0341- 2254265

GOVERNMENT OF INDIA  
CENTRAL WATER COMMISSION  
OFFICE OF THE EXECUTIVE ENGINEER  
DAMODAR DIVISION, APCAR GARDEN (WEST)  
ASANSOL-713304

No. DD/DB/Tender/2011-12 /1750-61

dated :- 29 / 07/2011

**NOTICE INVITING TENDER**

On behalf of The President of India, the under signed invites Sealed tender from reputed /registered experienced agency for the following work. Contractor are requested to submit their tenders in the official tender box or through registered post upto 1500 hrs on 25/08/2011

S.No• Description of work• Estimated Amount • Earnest Money (refundable)• Cost of Tender in Rs. • Period of contract • • **Construction of Cabin at Sites** • 1 • Konar • Rs. 66,230/- • Rs. 1,330/- • Rs. 150/- in cash • 90(Ninety) days • • 2 • Tenughat • Rs. 66,230/- • Rs. 1,330/- • -do- • - do - • • 3 • Ramgarh • Rs. 1,55990/- • Rs. 3,120/- • Rs. 500/- in cash • - do - • • The above tender will be opened at 15.30 Hrs. on the same day. Earnest money in favour of Executive Engineer, Damodar Division, Central Water Commission, Asansol as prescribed in the tender documents should be deposited with the tender in the Form of D.C.R. issued from any nationalized bank/ cash. The tender of the agency who do not deposit earnest money in the prescribed manner are liable to be rejected.

A complete set of tender document of the above work containing detailed terms and conditions, Schedule of quantity can be obtained by the eligible agencies from the office of the undersigned up to 1600 Hrs. on 24/08/2011 on all working days between 11.00 A.M. to 4.00 P.M. on submission of written application up to 16.00 Hrs. on 23/08/2011.

In case of above date of receiving and opening date of tender is declared holiday etc. the tender shall be received & opened on the next working day as per schedule time. More details are available on web site

[cwc-tender@mail.nic.in](mailto:cwc-tender@mail.nic.in) & [smdte@nic.in](mailto:smdte@nic.in).

( RAM NATH YADAV )  
EXECUTIVE ENGINEER

Copy along with enclose forwarded for information with request for board publicity through pasting on his office Notice board:-

1. The Director, SMD, CWC, New Delhi is requested to get published in CWC web site. Email for this purpose has already been sent.
2. The SE, HOC, CWC, Maithon Dam ( Jharkhand).
3. The E.E. Lower Ganga Division, CWC, Berhampore.
4. The S.D.E, Tenughat/Maithon/Midnapore/Suri/Durgapur/ Kolkata
5. The A.D. II, Head Quarter, Damodar Division, CWC, Asansol.
6. The AAO, A / B, Damodar Division, CWC, Asansol.
7. Notice Board, Damodar Division, CWC, Asansol

( RAM NATH YADAV )

## **ANNEXTURE – I**

### **DETAILS**

1• Name of work• Construction of Cabin •• 2• Estimated Amount• :-Rs. 66,230/-(Rupees Sixty six thousand two hundred thirty) only for SL.No 1 to 2, Rs. 1,55,990/-(Rupees One lakh fifty five thousand nine hundred ninety) only for SL. No. 3 •• 3• Cost of tender Document• :-Rs. 150/- ( Rupees One hundred fifty)only for Sl.No. 1 & 2 and Rs. 500/- ( Rupees five hundred) only for Sl.No. 3

•• 4• Earnest Money• :-Rs. 1,330/-(Rupees one thousand three hundred thirty ) only for SL.No 1 to 2, Rs. 3120/- (Rupees three thousand one hundred twenty ) only for SL. No. 3•• 5• Security Deposit• :- 05 % of the gross value of work shall be deducted from the final bill.

•• 6• Performance Guarantee• :- 5 % on the work order amount shall be deposited before commencement of work

•• 7• Time completion of work• :- 90 (Ninety) days from 7<sup>th</sup> date of issue of work order•• 8• Last date of receipt of application for issue of tender• :- 23/08/.2011 upto 16.00 Hrs

•• 9• Last date of sale of tender• :- Up to 16.00 Hrs. on 24/08/.2011

•• 10• Last date of receiving of tender• :- Upto 15.00 on 25/08/.2011

•• 11• Date of opening tender• :- On 25/08/.2011 at 15.30 hrs.

( if the opening date of tender happens to be a holiday under any circumstance the tender will be opened on the next working day at the same time)•• 12• Contractor can visit the working site before quoting rates for tender to assess the quantum of work if required••

EXECUTIVE ENGINEER

## SCHEDULE

### Name of work :- **Constructioun of Cabin**

Sl.

No•Sub- head and item of work• Qty. •Unit• **Konar**• •••• Rate supplied• quoted by agency• • 1• Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6.●

7.69●  
Cum●

2430.30●●● 2● Reinforcement cement concrete work in beams suspended floors, roofs having slope up to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement.●

2.26●  
Cum●

3673.85●●● 3● Reinforcement for RCC work including strightning,cutting,bending, placing in position and and binding all complete.Mild steel and Medium Tensile steel bars. ●

125●  
Kg●

41.50●●● 4● Centering and shuttering including strutting proping etc.and removal of suspended floors, roofs, landing balconies and access platform. ●

11.94●  
Sqm●

187.35●●● 5● Centering and shuttering including strutting proping etc.and removal of lintels, beams, plinth beams and cantilevers.●

4.22●  
Sqm●

162.65●●● 6● Cement plaster (in fine sand) 20mm thick cement plaster of mix 1:6.●

38.54●  
Sqm●

95.10●●● 7● Cement plaster (in fine sand) 12 thick cement plaster of mix 1:6.●

44.40●  
Sqm●

67.65●●● 8● Cement plaster skirting ( upto 30cm) with cement mortar 1:3 finished with a floating coat of of neat cement 18mm thick.●

9.36●  
Sqm●

168.50●●● 9● Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on new work ( two/ more coats) over & including priming coat with cement primer.●

65.08●  
Sqm●

41.55●●● 10● Finishing wall with water proofing cement paint of required shed new work ( two or more ) coats applied @ 3.84 Kg/10Sqm. ●

66.79●●

30.80●●●

Remarks : Add 43% for Konar under Jharkhand Region approved by CE, CPWD, Patna dated 12.01.2011 due to price escalation.

Authority of issuing the Tender

**Stamp with Signature.**

## SCHEDULE

### Name of work :- **Constructiuon of Cabin**

Sl.

No• Sub- head and item of work• Qty. • Unit• **Tenughat**• • • • • Rate supplied• quoted by agency• • • 1• Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6. •

7.69•

Cum•

2430.30• • • 2• Reinforcement cement concrete work in beams suspended floors, roofs having slope up to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement. •

2.26•

Cum•

3673.85• • • 3• Reinforcement for RCC work including strightning,cutting,bending, placing in position and and binding all complete.Mild steel and Medium Tensile steel bars. •

125•

Kg•

41.50• • • 4• Centering and shuttering including strutting proping etc.and removal of suspended floors, roofs, landing balconies and access platform. •

11.94•

Sqm•

187.35• • • 5• Centering and shuttering including strutting proping etc.and removal of lintels, beams, plinth beams and cantilevers. •

4.22•

Sqm•

162.65• • • 6• Cement plaster (in fine sand) 20mm thick cement plaster of mix 1:6. •

38.54•

Sqm•

95.10• • • 7• Cement plaster (in fine sand) 12 thick cement plaster of mix 1:6. •

44.40•

Sqm•

67.65• • • 8• Cement plaster skirting ( upto 30cm) with cement mortar 1:3 finished with a floating coat of of neat cement 18mm thick. •

9.36•

Sqm•

168.50• • • 9• Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on new work ( two/ more coats) over & including priming coat with cement primer. •

65.08•

Sqm•

41.55• • • 10• Finishing wall with water proofing cement paint of required shed new work ( two or more ) coats applied @ 3.84 Kg/10Sqm. •

66.79• •

30.80• • •

Remarks : Add 43% for Tenughat under Jharkhand Region approved by CE, CPWD, Patna dated dated 12.01.2011 due to price escalation.

Authority of issuing the Tender

Stamp with Signature.

## SCHEDULE

**Name of work :- Constructioun of Cabin**

Sl.

No• Sub- head and item of work• Qty. •Unit• **Ramgarh**• ••••• Rate supplied• quoted by agency• • 1• Earth work in excavation manually in foundation trenches ( not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil. •

10.06•  
Cum•

103.40••• 2• Supplying and filling in plinth with local sand under foundation trenches including watering, watering, ramming, consolidating and dressing complete. •

1.23•  
Cum•

301.50••• 3• Brick Soling with Jhama brick/ khoa of 15 cm rammed to 10 cm including watering as per direction of Engineer in charge. •

1.23•  
Cum•

3000.00••• 4• Providing and laying position cement concrete of specified grade excluding the cost of centering and shuttering – all work upto plinth 1:2:4 cement mortar. •

1.63•  
Cum•

3149.10••• 5• 1:2:4 PCC work of specified grade excluding the cost of centering and shuttering. All works in foundation up to plinth level. •

6.14•  
Cum•

2121.75••• 6• Filling available excavated earth ( excluding rock) in trenches, plinth, sides of foundation , , etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m. •

8.91•  
Cum•

45.70••• 7• Providing and laying damp proof course 40mm thick with Cement concrete 1:2:4•

3.38•  
Sqm•

144.15••• 8• Brick work in class designation 75 super structure above plinth level upto V level in all shapes and size in cement mortar 1:6. •

13.20•  
Cum•

2430.30••• 9• Reinforcement cement concrete work in beams suspended floors, roofs having slope up to 15 landings, balconies,shelves, chujja, lintels, bands plan window sills, staircases and spiral stair cases upto floor V level excluding the cost of centering ,shuttering, finishing and reinforcement. •

3.19•  
Cum•

3673.85••• 10• Reinforcement for RCC work including strightning,cutting,bending, placing in position and binding all complete.Mild steel and Medium Tensile steel bars. •

380•

Kg•

41.50•••• 11• Centering and shuttering including strutting propping etc.and removal of suspended floors, roofs, landing balconies and access platform. •

16.70•  
Sqm•

187.35•••• 12• Centering and shuttering including strutting propping etc.and removal of lintels, beams, plinth beams and cantilevers. •

11.92•  
Sqm•

162.65•••• 13• Cement concrete flooring 1:2:4 finishing sluary, but excluding the cost of nosing of steps etc. complete. •

15.00•  
Sqm•

192.95•••• 14• Cement plaster (in fine sand) 20mm thick cement plaster of mix 1:6. •

65.15•  
Sqm•

95.10•••• 15• Cement plaster (in fine sand) 12 thick cement plaster of mix 1:6. •

67.85•  
Sqm•

67.65••••

2

Sl.

No• Sub- head and item of work• Qty. • Unit• **Ramgarh**••••• Rate supplied• quoted by agency•• 16• Cement plaster skirting ( upto 30cm) with cement mortar 1:3 finished with a floating coat of neat cement 18mm thick. •

11.48•  
Sqm•

168.50•••• 17• Distemping with oil bound washable distemper of approved brand and manufacture to to give an even shade on new work ( two/ more coats) over & including priming coat with cement primer. •

65.15•  
Sqm•

41.55•••• 18• Finishing wall with water proofing cement paint of required shed new work ( two or more ) coats applied @ 3.84 Kg/10Sqm. •

66.85•  
Sqm•

30.80••••

Remarks : Add 43% for Ramgarh under Jharkhand Region approved by CE, CPWD, Patna dated dated 12.01.2011 due to price escalation.

Authority of issuing the Tender

**Stamp with Signature.**

Name of Firms.

Address.

PAN No.

Registration No.

Earnest Money.

D.D. No. & Date

**Signature of Tendered**

**GENERAL CONDITION FOR CONTRACT :**

1. Work should be done satisfactory as per specification & direction of Engineer in charge.

Payment should be made after submission of bill in triplicate after completion of satisfactory through A/C payee Cheque / DD.

No extra taxes will be paid.

5% performance guaranty should be deposited before commencement of work.

A security deposit @ 5% , Income tax @ 2% and Cont. Tax as per rule of the total value of work will be deducted from the final bill.

**( RAM NATH YADAV )**  
**Executive Engineer**