

GOVERNMENT OF INDIA  
CENTRAL WATER COMMISSION  
OFFICE OF THE EXECUTIVE ENGINEER  
DAMODAR DIVISION, APCAR GARDEN ( WEST)  
ASANSOL

No. DD /HQ/NIQ/2011-12/ 1368-78

Dated 18/06/2011

**NOTICE INVITING QUOTATION**

Sealed Quotations are hereby invited by the undersigned on behalf of the President of India from the local / reputed / experienced agencies to quoted their rates for **Construction of Water Tank at Konar** as per annexure – A ( copy enclosed) on the following terms and conditions.

The Quotation should reach to this office either by post or by hand or by dropping in to the tender box up to 15.00hrs. of 07/07/2011 and the same will be opened on the same day at 15.30 hrs. in presence of agencies or their authorized representative, who may be interested to be present at the time of opening of the quotations. Rates should be quoted both in words and figures. Cutting and overwriting, if any should be attested.

**TERMS AND CONDITIONS :-**

1. Works should be as per drawing, specification & direction of Engineer - in - charge.
2. The works should be completed within 30 days from the date of issue of work order.
3. The payment will be made through A/C payee Cheque / Demand Draft on submission of bills in triplicate after satisfactory completion of works.
4. The undersigned reserves the right to reject or accept any or all quotations without assigning any reason thereof.

Sd/-

( Ram Nath Yadav )  
Executive Engineer

Copy for information to :-

1. The Director, SMD, CWC, New Delhi. He is requested to get published in CWC web site. Email for this purpose has already been sent.
2. The SE, HOC, CWC, Maithon Dam ( Jharkhand).
3. The E.E. Lower Ganga Division, CWC, Berhampore.
4. The SDE, CWC, Maithon, Durgapur, Tenughat, Suri, Midnapore, Kolkata with instruction to paste on his notice board to publicity.
1. The AAO, A/B, Damodar Division, CWC, Asansol
2. Notice Board

## ANNEXURE - A

### Name of Work : Construction of Water Tank at Konar

SN	Sub-Head and item of work	Qty.	Rates of estimate	Rate to be quoted by the agencies.
1	Eart work in excavation manually in foundation trenches (not exceeding exceeding 1.5 in width and 10Sqm. on plan) including dressing of sides and disposal of surplus excavated soils as directed within a lead of 50m. In all kinds of soil	4.21 Cum	103.40	
2	Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete.	0.79 Cum	301.50	
3	Brick soling with jhama brick/ khoa of 15cm rammed to 10cm including watering as per direction of engineer in charge	0.79 Cum	2500.00	
4	Providing laying in position cement concrete of specified grade excluding the cost of centering and shuttering. - all work up to plinth level 1:2:4 Mix.	1.08 Cum	3257.45	
5	Brick work with FPS brick of class designation 75 in foundation and plinth in 1:6 Mix. .	1.80 Cum	2121.75	
6	Brick work with FPS brick of class designation 75 in superstructure above plinth level up to V level in all shapes and size in 1:6 Cement mortar.	2.50 Cum	2430.30	
7	Filling available excavated earth ( excluding rock) in trenches, plinth sides of foundation, etc in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming & watering, lead up to 50m & lift up to 1.5m.	0.56 Cum	45.70	
8	Reinforcement cement concrete work in beams suspended floors, roofs having slope up to 15" landings, balconies,shelves,chujja, lintels, bands plan window sills,staircases and sprial stair cases upto floor V level excluding the cost of centering,shuttering, finioshing and reinforcment width 1:2:4	0.82 Cum	3673.85	
9	Reinforcement for RCC work including strightning,cutting, bending, placing in position and binding all complete.Mild steel and Medium Tensil steel bard.	50 Kg	41.50	
10	Centering and shuttering including strutting, proping etc. and removal of form suspended floors, roofs, landings, balconies and access platform.	7.48 Sqm	187.35	
11	Cement Plaster with a Floating Coat of Neat Cement 15mm cement plaster on rough side of single or half brick wall finished with afloating of neat cement of Mix. 1:3.	16.80 Sqm	122.50	
12	20mm thick cement plaster 1.6	18.41 Sqm	67.65	
13	Circular Shape 500mm dia precast RCC manhole cover with frame LD-25	1No	575.00	

Remarks: Konar under Jharkhand region, the above estimated rate has been increased by 143% due to price escalation / cost index approved by the the CE,EZ- II,CPWD, Patna order, dated 12.01.2011.

( R.N.Yadav )  
Executive Engineer

