

GOVERNMENT OF INDIA
CENTRAL WATER COMMISSION
OFFICE OF THE EXECUTIVE ENGINEER
DAMODAR DIVISION, APCAR GARDEN (WEST)
ASANSOL-713304

No. DD/DB/Tender/2011-12 / 297-308

dated :- 21/01 /2012

NOTICE INVITING TENDER

Sealed item rate tenders are hereby invited by the Executive Engineer, Damodar Division, CWC, Asansol on behalf of President of India from Registered / experienced / reputed / competent / financially sound contractors / Companies / Firms / Joint Ventures fulfilling eligibility and qualification requirements specified in tendering for the below mentioned works of Damodar Division, CWC located at Asansol. The tender should be submitted up to 15.00 at **17.02.2012** and the same will be opened at 15.30 Hrs. on the same day.

S.No	Description of work	Estimated Amount	Earnest Money (refundable)	Cost of Tender in Rs.	Period of contract
Construction of Cabin at Telemetry Station,					
1	Giridih	Rs 2,77,454 /-	Rs 5550 /-	Rs 500 /- in cash	90 days
2	Phusro	Rs 2,77, 454/-	Rs 5550 /-	Rs 500/- in Cash	90 days
3	Nandadih	Rs 2,77, 454/-	Rs 5550/-	Rs 500/- in cash	90 days
4	Pupunki	Rs 2,77, 454/-	Rs 5550/-	Rs 500/- in cash	90 days

Earnest money in favour of Executive Engineer, Damodar Division, Central Water Commission, Asansol as prescribed in the tender documents should be deposited with the tender in the form of D.C.R. issued from any nationalized bank or by cash. The tender of the agency who do not deposit required earnest money in the prescribed manner are liable to be rejected.

A complete set of tender document of the above work containing detailed terms and conditions, Schedule of quantity can be obtained by the eligible agencies from the office of the undersigned up to 1600 Hrs. on **16/02/2012** on all working days between 11.00 A.M. to 4.00 P.M. on submission of written application up to 16.00 Hrs. on **15/02/2012**.

In case of above date of receiving and opening date of tender is declared holiday etc. the tender shall be received & opened on the next working day as per schedule time. More details are available on web site cwc-tender@mail.nic.in & smdte@nic.in.

(RAM NATH YADAV)
EXECUTIVE ENGINEER

Copy along with enclose forwarded for information with request to paste on their office Notice board for broad publicity :-

1. The Director, SMD, CWC, New Delhi is requested to get published in CWC web site. Email for this purpose has already been sent.
2. The SE, HOC, CWC, Maithon Dam (Jharkhand).
3. The E.E. Lower Ganga Division, CWC, Berhampore.
4. The S.D.E, Tenughat/Maithon/Midnapore/Suri/Durgapur/ Kolkata
5. The A.D. II, Head Quarter, Damodar Division, CWC, Asansol.
6. The AAO, A / B, Damodar Division, CWC, Asansol.
7. Notice Board, Damodar Division, CWC, Asansol

(RAM NATH YADAV)
EXECUTIVE ENGINEER

ANNEXTURE – I

DETAILS

1	Name of work	Construction of Cabin at Telemetry Station, Giridih, Phusro, Nandadih, Pupunki.
2	Estimated Amount	: - Rs. 2,77,454/-
3	Cost of tender Document	: - Rs. 500/- (Rupees five hundred) only
4	Earnest Money	: - Rs. 5,550/- (Rupees five thousand five hundred fifty) only
5	Security Deposit	: - 05 % of the gross value of work shall be deducted from the final bill.
6	Performance Guarantee	: - 5 % on the work order amount shall be deposited before commencement of work
7	Time completion of work	: - 90 (Ninety) days from 7 th date of issue of work order
8	Last date of receipt of application for issue of tender	: - up to 16.00 Hrs on 15/02/ 2012
9	Last date of sale of tender	: - Up to 16.00 Hrs. on 16/ 02 /2012
10	Last date of receiving of tender	: - Up to 15.00 on 17/02/ 2012
11	Date of opening tender	: - On 17/02/ 2012 at 15.30 hrs. (if the opening date of tender happens to be a holiday under any circumstance the tender will be opened on the next working day at the same time)
12	Contractor can visit the working site before quoting rates for tender to assess the quantum of work if required	

(RAM NATH YADAV)
EXECUTIVE ENGINEER

SCHEDULE

Name of work :- Construction of Cabin at Telemetry station, Girdih, Phusro, Nandadih. Pupunki.

Sl. No	Sub- head and item of work	Qty.	Unit	Rate supplied	quoted by agency	
					Rate	amount
1	Earth work in excavation manually in foundation trenches (not exceeding 1.5m in width and 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kinds of soil.	14.40	Cum	103.40		
2	Supplying and filling in plinth with local sand under foundation trenches including watering, ramming, consolidating and dressing complete.	3.10	Cum	301.50		
3	Brick Soling with FPS brick of class designation 75 in foundation and plinth in 1:6 Cement mortar .	3.10	Cum	2121.75		
4	1:2:4 PCC work with course sand and 20mm normal size stone aggregate excluding the cost of centering and shuttering, all works in foundation up to plinth level.	1.56	Cum	3257.45		
5	Centering & shuttering including strutting, propping etc & removal of form PCC work for foundations, footing etc.	4.00	Sqm	119.25		
6	Brick work with FPS brick of class designation 75 in foundation and plinth in 1:6 Cement mortar .	9.86	Cum	2121.75		
7	Filling available excavated earth in trenches, plinth, sides of foundation , etc. in layers not exceeding 20cm in depth	2.16	Cum	45.70		
8	1:2:4 DPC 50mm thick with course sand and 20mm normal size stone aggregate.	7.79	Sqm	178.05		
9	RCC 1:2:4 work with course sand and 20mm normal size stone aggregate for all work up to plinth level excluding the cost of centering, shuttering, finishing and reinforcement.	0.90	Cum	3359.60		
10	Centering and shuttering including strutting propping etc.and removal of from work for foundation, footings, bases of column etc. up to plinth level for mass concrete.	7.98	Cum	119.25		
11	RCC 1:2:4 work with course sand and 20mm normal size stone aggregate in column, pillar, pairs etc. above plinth and up to V floor levels excluding the cost of centering, shuttering, finishing and reinforcement.	1.28	Cum	3720.00		
12	Centering and shuttering including strutting propping etc.and removal of from column, pillars, piers etc.	20.40	Sqm	238.40		
13	RCC 1:2:4 work with course sand and 20mm normal size stone aggregate in roof, beams, lintels, chujja etc. up to floor five levels excluding the cost of centering, shuttering, finishing and reinforcement.	4.01	Cum	3673.85		
14	Centering and shuttering including strutting propping etc.and removal of from for roof, chujja etc. with water proof ply 12 mm thick.	29.95	Sqm	329.80		

contd. 2

Sl. No	Sub- head and item of work	Qty.	Unit	Rate supplied	quoted by agency	
					Rate	amount
15	Centering and shuttering including strutting propping etc.and removal of form for lintels, beams etc. with water proof ply 12 mm thick.	6.15	Sqm	319.10		
16	Reinforcement for RCC work including strighting, cutting, bending, placing in position and binding all complete upto and above plinth level for Mild tensile Medium steel bars.	1000	Kg	41.50		
17	Brick work in class designation 75 super structure above plinth level upto V level in 1:6 C. M. with course sand.	14.05	Cum	2430.25		
18	Filling available excavated earth in trenches, plinth, sides of foundation , etc. in layers not exceeding 20cm in depth along with carriage of earth by mechanical transport including loading, unloading & sacking at lead up to 4 Km.	10.50	Cum	115.69		
19	PCC 1:2:4 flooring/ pavement with 20mm normal size and in course sand including finishing complete.	1.50	Cum	3695.95		
20	Extra for making chequers of approved pattern on cement concrete floos, steps, landing , pavements etc.	15.00	Sqm	13.15		
21	15mm Cement plaster in course sand on rough side of single or half brick wall of Mix 1:6	63.70	Sqm	84.55		
22	15mm Cement plaster in course sand on rough side of single or half brick wall finished with a floating coat of neat cement of 1:4 Mix.	15.75	Sqm	110.70		
23	12mm Cement plaster in course sand of Mix 1:6	58.60	Sqm	72.70		
24	12mm Cement plaster in fine sand finished with a floating coat of neat cement of 1:4 Mix.	4.80	Sqm	97.90		
25	12mm Cement plaster in fine sand finished with a floating coat of neat cement of 1:3 Mix.	44.95	Sqm	107.80		
26	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade on new work (two or more coats) over & including priming coat with cement primer.	157.90	Sqm	41.55		
27	Finishing wall with water proofing cement paint of required shed new work (two or more) coats applied.	15.75	Sqm	30.80		
28	Providing & fitting door (Iron / Wooden as required) of specified standard size.	1	No	10000.00		
29	Providing & fitting window (Iron / Wooden as required) of specified standard size.	1	No	5000.00		

Remarks : Add 43% due to price escalation as per CPWD, Patna order No. 19 (2) /2011/73 dated 12.01.11 for Giridih,Phusro,Nandadih & Pupunki for Jharkhand Region except Sl. No. 28 & 29

Authority of issuing the Tender

Stamp with Signature.

GENERAL CONDITION FOR CONTRACT :

1. Work should be done satisfactory as per specification & direction of Engi. in charge.
2. Payment should be made after submission of bill in triplicate after completion of Work satisfactory through A/C payee Cheque / DD.
3. No extra taxes will be paid.
4. 5% performance guaranty should be deposited before commencement of work.
5. A security deposit @ 5% , Income tax @ 2% and Cont. Tax as per rule of the total value of work will be deducted from the final bill.

**(RAM NATH YADAV)
Executive Engineer**

1. Name of Firms.
2. Address.
3. PAN No.
4. Registration No.
5. Eligibility Criteria
6. Earnest Money.
D.D. No. & Date

