

I/70866/2021(1)



भारत सरकार/GOVERNMENT OF INDIA

केंद्रीय जल आयोग/CENTRAL WATER COMMISSION

अधिकासी अभियन्ता कार्यालय/OFFICE OF EXECUTIVE ENGINEER

मेघना अन्वेषण मंडल/MEGHNA INVESTIGATION DIVISION

E-mail: midcwc-meg@nic.in  
midcwc@gmail.com  
Tel: 0364-2521226  
Fax: 0364-2521226

**NOTICE INVITING QUOTATION**

Sealed quotations are hereby invited by the undersigned on behalf of the President of India for works as detailed below. **The quotations should reach in the Office of the undersigned on or before 22.09.2021 up to 16.00 hrs** and will be opened on **23.09.2021 at 10.30 hrs** in the presence of quotationers or their authorized representatives, if any.

The undersigned reserves the right to accept or reject any or all the quotations without assigning any reason thereof.

Sl. No.	Description and specifications of work	Quantity	Unit
1.	Construction of Approach Path and Installation of Gauge Post at Byrnihat Gauge site under Meghna Investigation Division, CWC as per the drawing attached as Annexure- 1	01	Nos.
2.	<b>Estimated cost: ₹ 1,97,000.00 (Rupees One lakh ninety-seven thousand only)</b>		

**Terms & Conditions:**

- The quotations duly signed should be properly sealed and dropped in quotation Box in the office of the Executive Engineer, Meghna Investigation Division, CWC, 4<sup>th</sup> Floor MSHFCSL Building, Nongrim Hills, Shilong-793003. The sealed envelope should be super scribed **“Construction of Approach Path and Installation of Gauge Post at Byrnihat Gauge site under MID due on 22.09.2021 up to 16.00 hrs”**.
- Only those firms having GST number are eligible to submit their quotation.
- The undersigned does not bind him to accept the lowest quotation and reserve the right to accept or reject any or all the quotations without assigning any reason thereof.
- All materials required for the work are to be supplied by the contractor. The material must be of standard quality and as per specifications and free from all defects. The material if found defective subsequently or not conforming to the specifications as stated above, have to be replaced by the firm without any additional charges.
- Before starting the work, material shall be got approved from the Sub-Divisional Engineer(HQ), MID, CWC, Shillong.
- The work shall have a warranty period of minimum six months from the date of construction/installation.
- The work is estimated to cost ₹ 1,97,000/- (Rupees One lakh ninety-seven thousand only). This estimate, however, is given merely as rough guide.
- The quantity of materials may be increased or decreased at the time of work order without assigning any reason thereof.
- Successful bidder needs to submit the Security deposit @ 5% of Bid amount. Security Deposit will be valid after 6 months from the date of completion of work.
- The work of “Construction of Approach Path and Installation of Gauge Post at Byrnihat Gauge site” in all respects should be completed within 90 days from the date of issue of work order.
- The rate quoted should be inclusive of all duties, taxes and other levies as applicable.
- The validity of quotation for acceptance shall be 90 days and rate quoted should be remains valid for 180 days from the date of opening.

I/70866/2021(1)

13. The rate should be quoted both in words and in figures. Corrections/overwriting in the quotation, if any, shall be made by initiating, dating and re-writing.
14. Payment will be made by PFMS, online payment on production of bill in triplicate after satisfactory completion of work in all respect and as per specification. Agency may please produce Bank account details Mandate form along with bill.

**Executive Engineer  
MID, CWC, Shillong**

**Copy to:**

1. The Superintending Engineer, Meghna Circle, CWC, Silchar.
2. The Sub-Divisional Engineer, MISD-I, CWC, Shillong.
3. Accounts Branch, Meghna Investigation Division, CWC.
4. Notice board of O/o Executive Engineer, MID, CWC, Shillong.
5. Details of this NIQ are also available on CPP/CWC Portal.

I/70866/2021(1)

**Bill of Quantities (BOQ)**

**Construction of Approach Path and Installation of Gauge Post at Byrnihat Gauge site under Meghna Investigation Division, CWC, Shillong:**

Sl. No.	Description and specifications of item	Unit	Quantity	Rate (₹)	Amount (₹)
<b>(A) Construction of approach path at Byrnihat Gauge site under MID, CWC, Shillong.</b>					
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 Sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil.	Cum	15.60		
2	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement: 6 coarse sand: 12 graded stone aggregate 20 mm nominal size) upto plinth level with, Cement mortar 1:6 (1 cement: coarse sand).	Cum	1.50		
3	Providing and laying cement concrete in kerbs, steps and the like at or near ground level excluding the cost of centring, shuttering and finishing: 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	Sqm	14.10		
4	Centring and shuttering including strutting, propping etc. and removal of form work for: Foundations, footings, bases for columns.	Rm	15.60		
<b>(A) Total amount for construction of approach path (in ₹)</b>					
<b>(B) Installation of Gauge Post at Byrnihat Gauge site under Meghna Investigation Division, CWC, Shillong</b>					
1	Earthwork in excavation upto a depth of 2m below the existing ground level for foundation trenches of foundations, footings of column/ walls, retaining walls, septic tank etc. including bailing out water where necessary and removal of surplus earth with all lead and lifts as directed and specified for the following classification of soils. (c) In soft or laminated rock or medium shale.	Cum	0.324		
2	Earthwork in filling including necessary carriage, watering, ramming etc. complete as directed and specified. (b) With available excavated earth including breaking of clods, consolidating each layer by ramming and watering with all lead and lifts.	Cum	0.108		
3	Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in foundation bed for footing steps, walls, brick works etc. as directed and specified including dewatering if necessary, and curing complete (shuttering where necessary shall be measured and paid separately).	Cum	0.27		

I/70866/2021(1)

	(a) In prop. 1:3: 6 (1 cement: 3 coarse sand: 6 coarse agg. by volume (using mixture machine).				
4	15 mm thick Cement plaster in single coat on rough side of single or half brick wall for interior plastering up to 1st floor level including arises, internal rounded angles, not exceeding 80mm girth and finished even and smooth including curing complete as directed. (a) In cement mortar 1:3.	Sqm	0.72		
5	Applying priming coat over new wood and wood based surfaces over 100mm in girth/width after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter, sand papering and knotting. (a) With ready mixed paint, Wood primer.	Sqm	0.74		
6	Painting two coats (excluding priming coat) on new wood and wood based surface with enamel paint of approved brand and manufacture (Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac) to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matter sand papering and stopping. (a) Surfaces over 100mm in width or girth.(i) General purpose (Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac).	Sqm	0.74		
Amount for installation of 01 Gauge post (in ₹)					
Total no. of Gauge post =10 Nos.					
(B) Amount for installation of 10 Nos. Gauge Post (in ₹)					
Total amount for Construction of Approach Path and Installation of Gauge Post (A+B) (in ₹)					
GST					
Grand Total (in ₹)					

(Rupees - - - - - only)

GST No of the agency:

Pan No .of the agency:

(Signature of agency with seal)