

I/88911/2022(1)



भारत सरकार/GOVERNMENT OF INDIA
 केंद्रीय जल आयोग/CENTRAL WATER COMMISSION
 अधिशासी अभियन्ता कार्यालय/OFFICE OF EXECUTIVE ENGINEER
 मेघना अन्वेषण मंडल/MEGHNA INVESTIGATION DIVISION

E-mail: midcwc-
 meg@nic.in
 midcwc@gmail.com
 Tel: 0364-2521226
 Fax: 0364-2521226

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the President of India for works as detailed below. **The quotations should reach in the Office of the undersigned on or before 30.03.2022 up to 1030 hrs** and will be same day at **1500 hrs** in the presence of quotationers or their authorized representatives, if any. ^{opened on}

The undersigned reserves the right to accept or reject any or all the quotations without assigning any reason thereof.

Sl. No.	Description and specifications of work	Quantity	Unit
1.	Renovation/Repair of Gauge Hut and CC steps at Dawki Site under MID, CWC, Shillong.	01	No.
2.	Estimated cost: ₹ 3,98,720.00 (Rupees Three Lakh Ninety-Eight Thousand Seven Hundred Twenty only).		

Terms & Conditions:

1. The quotations duly signed should be properly sealed and dropped in quotation Box in the office of the Executive Engineer, Meghna Investigation Division, CWC, 4th Floor MSHFCSL Building, Nongrim Hills, Shillong-793003. The sealed envelope should be super scribed "Renovation/Repair of Gauge Hut and CC steps at Dawki Site under MID, CWC, Shillong due on 30.03.2022 up to 1500 hrs".
2. Only those firms having GST number are eligible to submit their quotation.
3. The undersigned does not bind him to accept the lowest quotation and reserve the right to accept or reject any or all the quotations without assigning any reason thereof.
4. All materials required for the work are to be supplied by the contractor. The material must be of standard quality and as per specifications and free from all defects. The material if found defective subsequently or not conforming to the specifications as stated above, have to be replaced by the firm without any additional charges.
5. Before starting the work, material shall be got approved from the Sub-Divisional Engineer, MISD-1, CWC, Shillong.
6. The work shall have a warranty period of minimum two months from the date of construction/ installation.
7. **The work is estimated to cost ₹ 3,98,720/- (Rupees Three Lakh Ninety-Eight Thousand Seven Hundred Twenty only).** This estimate, however, is given merely as rough guide.
8. The quantity of materials may be increased or decreased at the time of work order without assigning any reason thereof.
9. Successful bidder needs to submit the Security deposit @ 5% of Bid amount.
10. The work of "Renovation/Repair of Gauge Hut and CC steps at Dawki Site under MID, CWC, Shillong" in all respects should be completed within 30 days from the date of issue of work order.
11. The rate quoted should be inclusive of all duties, taxes and other levies as applicable.

I/88911/2022(1)

12. The validity of quotation for acceptance shall be 90 days and rate quoted should be remains valid for 180 days from the date of opening.
13. The rate should be quoted both in words and in figures. Corrections/overwriting in the quotation, if any, shall be made by initiating, dating and re-writing.
14. The relevant office orders issued by State Government of Meghalaya and of local authority viz. Village Headman, etc. needs to be complied by the successful bidder itself.
15. Payment will be made by PFMS, online payment on production of bill in triplicate after satisfactory completion of work in all respect and as per specification. Agency may please produce Bank account details Mandate form along with bill.

Signed by Ashish Tripathi

Date: 23-03-2022 16:08:50

~~Executive Engineer~~
Executive Engineer
MID, CWC, Shillong

Copy to:

1. The Superintending Engineer, Meghna Circle, CWC, Silchar.
2. The Sub-Divisional Engineer, MISD-I, CWC, Shillong.
3. Accounts Branch, Meghna Investigation Division, CWC.
4. Notice board of O/o Executive Engineer, MID, CWC, Shillong.
5. Details of this NIQ are also available on CPP/CWC Portal.

I/88911/2022(1)

Bill of Quantities (BOQ)**Renovation/Repair of Gauge Hut and CC steps at Dawki Site under MID, CWC, Shillong:**

Sl. No.	Description and specifications of item	Unit	Quantity	Rate (₹)	Amount (₹)
(A) Renovation/Repair of Gauge Hut at Dawki Site.					
1	Dismantling all types of ceiling, partition and wall lining and stacking the materials as directed by the department for all levels.	Sq.m	42.7		
2	Dismantling and removing the existing door and window frame (chowkat) both wooden and steel of different sizes without damaging the walls and removing the frame and necessary repairs to the edges of the walls as directed for all levels. (i) Area of door/window up to 3.00sq.m.	Each	3		
3	Dismantling all types of corrugated/ trapezoidal sheet roofing including ridges, hips, valleys and gutters etc. and stacking the materials as directed by the department for all levels.	Sq.m	16.56		
4	Providing dressed wood work in post, walls, battens, post plate bressumers etc. including supplying and fixing with spikes, nails, bolt and nuts of 12mm dia (M.S) and required length etc. complete with kiricide oiling two coats to faces in contact with C.C or masonry (M.S flats, angle cleats and bolt and nuts required for flats, angle cleats wherever use shall be measured and paid separately). (d) With White pinewood	Cu.m	0.2745		
5	Providing Pre Painted Galvanized Iron Sheet four sides of wall (PPGI) (Dyna roof / Sathyam/ Durakolor/ Century Wells/Prestar/Wonder Roof make or equivalent) at all levels including supplying, fitting and fixing with self-drilling, self-tapping screws complete. (Roof trusses, purlins etc. to be measured and paid separately). (e) 0.60 mm thick	Sq.m	33.55		
6	Providing single layer bamboo-mat ceiling with lattice-pattern jaffri or mesh size 40mmx 40mm made out of bamboo slips of size 5mmx2mm size at bottom stiffened with bamboo slip of 25 mm x 5 mm size. (Ceiling joist to be measured and paid separately).	Sq.m	12		
7	Providing Pre Painted Galvanized Iron Sheet Roofing (PPGI) (Dyna roof / Sathyam/ Durakolor/ Century Wells/Prestar/Wonder Roof make or equivalent) at all levels including supplying, fitting and fixing with self-	Sq.m	16.56		

I/88911/2022(1)

	drilling, self-tapping screws complete. (Roof trusses, purlins etc. to be measured and paid separately). (e) 0.60 mm thick.				
8	Providing, fitting and fixing in position plywood / hardboard partition walls with 6mm thick ply board / hardboard (best) with horizontal and vertical Sal battens of size 50mm x 80mm spaced at not more than 1.20m apart with necessary nails, wood screws, bolts etc. complete as directed by the Department for all levels (Painting/Varnishing to be measured and paid separately).	Sq.m	33.55		
9	Painting two coats (excluding priming coat) on new wood and wood based surface with enamel paint of approved brand and manufacture (Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac) to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matter sand papering and stopping. (b) Surfaces up to 100mm in width or girth. (i) General purpose (Asian paint/ Bergerpaint/ ICI paint/ J & N paint/ Nerolac).	Sq.m	3.89351		
10	Painting two coats on new C.G.I. sheets with ready mixed anticorrosive paint of approved brand and shade suitable for painting over G.C.I sheets to give an even shade including the cleaning the rust patches with emery paper, dust, dirt, grease and other foreign matter with water complete.	Sq.m	53.16		
(A) Total amount for Renovation/Repair of Gauge Hut at Dawki Site (in ₹)					
(B) Repair and Maintenance of CC steps at Dawki Site					
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil.	Cum	20.10		
2	Providing and laying cement concrete in kerbs, steps and the like at or near ground level excluding the cost of centering, shuttering and finishing: 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	Cum	20.10		
3	Centering and shuttering including strutting, propping etc. and removal of form work for: Foundations, footings, bases for columns.	Sqm	20.10		
(B) Repair and Maintenance of CC steps at Dawki Site (in ₹)					
Total amount for Renovation/Repair of Gauge Hut and Repair and Maintenance of CC steps at Dawki Site (A+B) (in ₹)					
GST					
Grand Total (in ₹)					

(Rupees ----- only)

GST No of the agency:
Pan No .of the agency:

(Signature of agency with seal)