भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग ऊपरीब्रहमपुत्रमंडल, डिब्र्गढ



Government of India Ministry of Jal Shakti Department of Water Resources, RD & GR Central Water Commission Upper Brahmaputra Division, Dibrugarh

File No.04/07/NIQ/2022-UBD/ 3552-56

Dated: 22.08.2024

उद्धरण आमंत्रण सूचना /NOTICE INVITING QUOTATION

Name of Work: "Modification of Level-II Lab at Naharlagun, under UBD, CWC, Dibrugarh, Assam during 2024-25."

भारत के राष्ट्रपति की ओर से अधिकृत सेवा प्रदातायों से (जो निम्नलिखित निबंधन व शर्तें पूरी करते हो सीलबंद उद्धरण उपरोक्त कार्य हेतु आमंत्रित किए जाते है।

For on behalf of the President of India, Sealed quotations are invited for the above work by the undersigned from authorized/ reputed firms as per the following terms and conditions: -

नियम एवं शर्तें /Terms & Conditions:-

- 1. उपरोक्त कार्य ऊपरी ब्रह्मपुत्र मंडल, केंद्रीय जल आयोग, कार्यालय के अन्तर्गत Level-II Lab, नहार्लगुन में स्तीथ किया जाना है।
 - Above work shall be executed at the Level-II Lab at Naharlagun, under Upper Brahmaputra Division, CWC, Dibrugarh.
- 2. उपरोक्त कार्य को फॉर्म संख्या-2 मे बताए गए विवरण के अनुसार किया जाना है। Above work shall be executed as given in Form-2.
- 3. उपरोक्त कार्य के लिए बनाये गए प्राक्कलन के अनुसार कार्य में लगभग Rs 1,76,090/- रूपय , (GST सहित) का खर्चा आना सम्भावित है |
 - The estimated cost for above repair work is worked out to be approx. Rs 1,76,090/- (inclusive of GST)
- 4. सभी उद्ध्यरणकर्ता को दरें उद्ध्यरण करने से पूर्व कार्य स्थल का दौरा करने कि सलाह दी जाती है तत्पश्चात उद्धृत दरों मे कोई भी बदलाव मान्य नहीं होगा।
 - All bidders are advised to visit the work site before quoting the rates. Thereafter, no change in the quoted rates will be allowed.
- 5. हस्ताक्षरित व सीलबंद उद्धरण "अधिशासी अभियंता कार्यालय,ऊपरी ब्रह्मपुत्र मंडल, केंद्रीय जल आयोग, डिब्र्गढ़, असम, पिन-786003" मे दिनांक 07.09.2024 को दोपहर 15:00 बजे या उससे पूर्व प्राप्त हो जानी चाहिए जिसे उसी दिन शाम 16:00 बजे अधोहस्ताक्षरी अथवा प्राधिकृत प्रतिनिधि द्वारा आपूर्तिकर्ता या उनके प्रतिनिधि की उपस्थिती में खोली जाएगी।

The Quotation confirming to specifications duly signed should reach "O/O Executive Engineer, CWC, UBD, Dibrugarh, Assam, PIN-786003" on or before 07.09.2024 (15:00hours) and will be opened on the same day at 16:00 hours in the presence of supplier or their authorized representatives as feasible.

कनमगर,पोस्टऑफिस-सी.आर.बिल्डिंग,

डिब्र्गॅढ,असम-786003 दूरभाष: 0373-2950536

ई मेल:<u>ubd-cwc-asm@nic.in/</u> ubddbrcwc@gmail.com

जल संरक्षण-सुरक्षित भविष्य



Page 1 of 10

Jibon Phukan Nagar, P.O:C.R. Building, Dibrugarh, Assam - 786003

Tel: 0373-2950536

E-mail: <u>ubd-cwc-asm@nic.in/ubddbrcwc@gmail.com</u>

♦Conserve Water- Save Life

भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग ऊपरीब्रहमप्त्रमंडल, डिब्रगढ



Government of India
Ministry of Jal Shakti
Department of Water Resources, RD & GR
Central Water Commission
Upper Brahmaputra Division, Dibrugarh

6. उद्ध्यरणकर्ता अपने उद्ध्यरण को Level-II Lab, सुबनिसरी उपमंडल, केंद्रीय जल आयोग, नाहरलागुन, अरुणाचल प्रदेश-791110, के कार्यालय में भी जमा कर सकते हैं, पर सभी प्राप्त दरें को, अधिशासी अभियंता कार्यालय,ऊपरी ब्रह्मपुत्र मंडल, केंद्रीय जल आयोग, डिब्रूगढ़,असम,िपन-786003 के कार्यालय में ही खोली जायेगी, जैसा की बिंदु संख्या-05 में लिखा गया हैं।

Bidders can also submit their bids at the Office of Sub-Divisional Engineer, Subansiri Sub-Division, CWC, Naharlagun. However, all the bids shall be opened in the O/o Executive Engineer, CWC, UBD, Dibrugarh, Assam, PIN-786003 as per details mentioned at Point No. 05.

- 7. निर्धारित तिथि एवं समय के उपरांत प्राप्त होने वाले उद्धरण स्वीकार नहीं किये जायंगे | Quotation received after specified date and time will not be accepted.
- 8. कार्यआदेश जारी होने के 60 दिनों के भीतर उपरोक्त कार्य पूर्ण करना होगा,तत्पश्चात जी॰सी॰सी॰ के खंड 2के अनुरूप जुर्माना लगाया जाएगा जो कि आपूर्तिकर्ता/कांट्रैक्टर के बिल भुगतान से काट लिया जाएगा। जुर्माना 1% प्रतिमाह की दर से विलंब प्रतिदिन के आधार पर कांट्रैक्टर के द्वारा की गयी देरी की वजह से हुई क्षिति को देखते हुए मापा जाएगा जो कि अधिकतम स्वीकृत धनराशि के 10% मूल्य तक हो सकता है।

The work will have to be completed within 60 days from the date of issuance of the work order, failing in which; appropriate penalty as per Clause 2 of GCC may be deducted from the payment with maximum rate @ 1% (one percent) per month of delay to be computed on per day basis based on quantum of damage suffered due to stated delay on the part of Contractor, subjected to maximum of 10% of the accepted Tendered Value.

- 9. केन्द्रीय लोक निर्माण विभाग 2019व् समय समय पर उसके आगामी सभी संशोधनों के सभी नियम सारे निविदाकारों /सफल निविदाकारों के लिए बाध्य होंगे |
 - Rules/provisions of CPWD Works Manual 2019 and its subsequent amendments from time to time will be applicable/ binding on all bidders and on successful bidder.
- 10. चोरी, दुर्घटना, प्राकृतिक आपदा अथवा अन्य किसी भी कारण से उपकरण/सामग्री एवं जान-माल के नुकसान के दावे किसी भी सूरत में विभाग द्वारा स्वीकृत नहीं किए जाएँगे।

Claim/claims of damages or loss of the equipment & material and life due to theft, accident or natural calamity or any other reasons whatsoever shall not be entertained by the Department.

- 11. उदवरित दरें गंतव्य स्थान तक (FOR Destination) तथा समस्त कर एवं ड्यूटिज सहित होनी चाहिए। The rates should be quoted F.O.R. destination inclusive of all taxes and duties
- 12. उद्धरण सीलबंद लिफाफे में रखी जानी चाहिए तथा लिफाफे पर कार्य का नाम लिखा होना चाहिए।

वीक्ल्फ्र्कननगर,पोस्टऑफिस-सी.आर.बिल्डिंग,

र्डब्रुगढ, असम- 786003 दूरभाष: 0373-2950536

ई मेल:<u>ubd-cwc-asm@nic.in/</u> <u>ubddbrcwc@gmail.com</u>

जल संरक्षण-सुरक्षित भविष्य



Jibon Phukan Nagar, P.O.C.R. Building, Dibrugarh, Assam - 786003

Tel: 0373-2950536

E-mail: <u>ubd-cwc-asm@nic.in/</u> <u>ubddbrcwc@gmail.com</u>

♦Conserve Water- Save Life**♦**

Page 2. af 10

भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग ऊपरीब्रहमप्त्रमंडल, डिब्र्गढ



Government of India Ministry of Jal Shakti Department of Water Resources, RD & GR Central Water Commission Upper Brahmaputra Division, Dibrugarh

The sealed quotation cover should be super scribed with the words "Modification of Level-II Lab at Naharlagun under UBD, CWC, Dibrugarh, Assam during 2024-25"

13.भारत के राष्ट्रपति की ओर से अधोहस्ताक्षरी न्यूनतम या किसी अन्य उद्धरण को बिना कारण बताए अस्वीकार और मात्रा में परिवर्तन का अधिकार सुरक्षित रखते है।

On behalf of President of India, undersigned reserves the right to reject the lowest or quotation and to alter the quantity without assigning any reason thereof.

14. उक्त कार्य हेतु जारी कार्यादेश 7 दिन की नोटिस अविध के बाद बिना कोई कारण बताये किसी भी समय निरस्त किया जा सकता है।

The work order issued for the above work may be cancelled at any time after 7 days' notice period without assigning any reason or thereof.

- 15. उद्धरण की दरें 90 दिनों तक वैध होंगे। The rates shall be valid for 90 days minimum from the date of opening of the quotation.
- 16. दरों का उल्लेख शब्दों तथा अंकों दोनों में किया जाना होगा। Rates should be mentioned both in words and figures
- 17. भुगतान प्रभारी इंजीनियर द्वारा किए गए कार्य से संतुष्टि के बाद PFMS(NEFT/ RTGS) के माध्यम से किया जाएगा। जिस बैंक खाते में भुगतान किया जाना है, उस खाते का Self-attested Bank Mandate फॉर्म अनिवार्य रूप से कोटेशन के साथ लगाना है।

The payment will be made through PFMS mode only (NEFT/RTGS) after satisfactory completion of work. Self-attested Bank Mandate form where payment is to be credited shall be mandatorily attached.

- 18. सभी सुधारों और अधिलेखन को विधिवत रूप से सत्यापित किया जाना चाहिए। All the corrections and over writings should be duly attested.
- 19. सरकार के नवीनतम आदेशों के अनुसार जीएसटी एवं आयकर पर टीडीएस भुगतान के समय बिल से काट लिया जाएगा। इसलिए, उद्धरण के साथ पैन और जीएसटी पंजीकरण की प्रतियां उद्धरणके साथ संलग्न करना है अन्यथा उद्धरण को अस्वीकार कर दिया जाएगा।

TDS on income tax as per latest govt. orders / GST @ applicable rates will be deducted from the bill at the time of payment. Therefore, copies of the PAN and GST registration to be enclosed along with quotation, failing which the quotation will be rejected.

20. उदवरित दरें सभी करों एवं उपकरों सहित होना चाहिए तथा इस प्रकार की किसी भी मद हेतु अलग से कोई भी देय स्वीकार्य नहीं होगा।

The rates quoted should include all the taxes and surcharges. No other claims will be entertained in this regard.

बिनफूकननगर,पोस्टऑफिस-सी.आर.बिल्डिंग,

डिब्रगढ, असम-786003 दूरभाष: 0373-2950536

ई मेल:<u>ubd-cwc-asm@nic.in/</u> <u>ubddbrcwc@gmail.com</u> ∙जल संरक्षण-सुरक्षित भविष्य∙



Jibon Phukan Nagar,P.O:C.R. Building, Dibrugarh, Assam - 786003 Tel: 0373-2950536

E-mail: <u>ubd-cwc-asm@nic.in/ubddbrcwc@gmail.com</u>

♦Conserve Water- Save Life**♦**

lage 3 of .10

भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग ऊपरीब्रहमप्त्रमंडल, डिब्रूगढ



Government of India Ministry of Jal Shakti Department of Water Resources, RD & GR Central Water Commission Upper Brahmaputra Division, Dibrugarh

21. कार्य प्रदान करने के बाद भी, यदि फर्म निर्धारित समय सीमा के भीतर कार्य करने में विफल रहती है तो इसके कारणों को लिखित रूप में प्रभारी अभियंता को प्रस्तुत किया जाएगा। प्रभारी अभियंता को अपने विवेक से प्राप्त प्रतिक्रिया के आधार पर उपरोक्त फर्म के खिलाफ कोई भी आवश्यक कार्रवाई) निलंबन, ब्लैकलिस्टिंग आदि (करने का पूरा अधिकार सुनिश्चित रहेगा।

Even after the award of the work, if firm fails to take up the work within the stipulated time frame; the reasons of the same shall be furnished to Engineer-in-Charge in writing. The Engineer In-Charge at its discretion has full authority to take any necessary action against the firm (suspension, blacklisting etc.) based on the response received.

22. निविदाकार द्वारा किसी भी प्रकार का प्रत्यक्षया अप्रत्यक्षप्रेरण, कपटपूर्ण व्यवहार निविदा को किसी भी समय निरस्त करने की दिशा में ले जा सकता है एवं निविदाकार को भविष्य में केंद्रीय जल आयोग के सभी कार्यों से blacklist भी किया जा सकता है।

Canvassing, soliciting, fraud practices, suppression of facts, stating wrong facts and fraudulent practice by the tenderer may lead to rejection of the tender at any stage of the work and may lead to blacklisting for all future CWC works.

- 23. कोटेशन फार्म1- एवं 2 को पूर्णतया :भरकर ही जमा करना होगा, संशयात्मक स्थिति एवं अधूरी सूचना की स्थिति में कोटेशन को अस्वीकार कर दिया जाएगा।

 Quotation Form-1 and 2 have to be submitted only after complete filling of given Form, in case of doubtful status and incomplete information, the quotation will be rejected.
- 24. मेक इन इंडिया को प्रोत्साहित करने और आय और रोजगार बढ़ाने की दृष्टि से भारत में वस्तुओं और सेवाओं के विनिर्माण और उत्पादन को बढ़ावा देने के लिए, औद्योगिक नीति और संवर्धन विभाग, वाणिज्य और उद्योग मंत्रालय, जीएफआर) 153 के नियम 2017!!!) के अनुसार, स्थानीय आपूर्तिकर्ताओं के माध्यम से खरीद के आदेश जारी किए। इन आदेशों के प्रावधानों के अनुसार, निर्दिष्ट तरीके से खरीद संस्थाओं द्वारा की जाने वाली सभी खरीद में स्थानीय आपूर्तिकर्ताओं को खरीद प्राथमिकता दी जाएगी।

To encourage Make in India and promote manufacturing and production of goods and services in India with a view to enhancing income and employment, the Department of Industrial Policy and Promotion, Ministry of Commerce and Industry, pursuant to Rule 153(iii) of the GFR 2017, have issued orders for procurement through local suppliers. As per the provisions of these orders, purchase preference shall be given to local suppliers in all procurements undertaken by procuring entities in the manner specified in the said orders. Hence Bidders are required to submit proof of local vendor by furnishing their permanent office address.

25. सेवा प्रदाता का कार्यालय कंसाइनी के राज्य में स्थित होना चाहिए। दस्तावेजी साक्ष्य प्रस्तुत करना होगा।

An office of the Service Provider must be located in the state of Consignee. Documentary evidence to be submitted.

मीबन्फूकननगर,पोस्टऑफिस-सी.आर.बिल्डिंग,

डिब्र्गढ, असेम-786003 दूरभाष: 0373-2950536

ई मेल:<u>ubd-cwc-asm@nic.in/</u> <u>ubddbrcwc@gmail.com</u> ∳जल संरक्षण-सुरक्षित भविष्य∳



Jibon Phukan Nagar,P.O:C.R. Building, Dibrugarh, Assam - 786003 Tel: 0373-2950536

E-mail: <u>ubd-cwc-asm@nic.in/ubddbrcwc@gmail.com</u>

♦Conserve Water- Save Life♦

Page 4 of 10

भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग ऊपरीब्रहमप्त्रमंडल, डिब्रगढ



Government of India Ministry of Jal Shakti Department of Water Resources, RD & GR Central Water Commission Upper Brahmaputra Division, Dibrugarh

26. भारत सरकार के आदेश संख्या F-9/4/2020-PPD दिनांक 12.11.2020 के तहत उपरोक्त कार्य के लिए कोई EMD देय नहीं है, हालांकि सफल निविदाकार को स्वीकृतदर की 3% राशि निष्पादन गारंटी के रूप में अधिशासी अभियंता, ऊपरी ब्रह्मपुत्र मंडल, केंद्रीय जल आयोग, डिब्रूगढ़ के नाम पर DD/FDR द्वारा जमा करनी होगी जो कि कार्य समाप्त होने के बाद 120 दिन तक वैध होनी चाहिए। As per Government of India order No. F. 91412020-PPD dated 12.11.2020 EMD has been exempted. However, successful quotation or have to submit performance guarantee within 5 working days of acceptance of work, amounting to 3% of accepted contract value in the form of DD/FDR in favor of Executive Engineer, Upper Brahmaputra Division, Central Water

(अभिजीत काशलीवात् अधिशासी अभियंत

प्रतिलिपि

1. अधीक्षण अभियंता (समन्वय), ब्रह्मपुत्र बेसिन संगठन, केंद्रीय जलआयोग, गुवाहटी - 781014

Commission at Dibrugarh valid up-to 120 days beyond the date of expiry of contract.

2. अधीक्षण अभियंता, जल विज्ञानीय प्रेक्षण एवं अन्वेषण परिमंडल, केंद्रीय जल आयोग, गुवाहटी - 781014

3. सहायक अधिशासी अभियंता(मुख्यालय),ऊपरी ब्रह्मपुत्र मंडल,केंद्रीय जल आयोग, डिब्रूगढ़, असम – 786003

4. सहायक अधिशासी अभियंता, सुबनसिरी उपमंडल, केंद्रीय जल आयोग, नाहरलागुन, अरुणाचल प्रदेश ।— 791110- for necessary follow up action.

5. लेखा शाखा, ऊपरी ब्रह्मपुत्र मंडल, केंद्रीय जल आयोग,डिब्रूगढ़ असम- 786003

भभिजीत काशलीवाल) अधिशासी अभियंता

Page 5 of 10

जीबनफूकननगर,पोस्टऑफिस-सी.आर.बिल्डिंग, डिब्रूगढ,असम-786003 दूरभाष: 0373-2950536 ई मेल:<u>ubd-cwc-asm@nic.in/</u>

इ मल:<u>ubd-cwc-asm@nic.in/</u> ubddbrcwc@gmail.com •जल संरक्षण-स्रक्षित भविष्य•



Jibon Phukan Nagar,P.O:C.R. Building, Dibrugarh, Assam - 786003 Tel: 0373-2950536

E-mail: <u>ubd-cwc-asm@nic.in/ubddbrcwc@gmail.com</u>

♦Conserve Water- Save Life**♦**

भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग ऊपरीब्रहमप्त्रमंडल, डिब्रगढ



Government of India Ministry of Jal Shakti Department of Water Resources, RD & GR Central Water Commission Upper Brahmaputra Division, Dibrugarh

Form Number-1 / फॉर्म संख्या: -1

Name of Work/कार्य का नाम: "Modification of Level-II Lab at Naharlagun under UBD, CWC, Dibrugarh, Assam during 2024-25"

[
1	Name of Company/ Firm / Agency:	
2	Name of proprietor / Director of Company / Firm / agency:	
3	Full Address of Reg. Office:	
4	Telephone No.	
5	E-Mail Address:	
6	Full address of Operating/ Branch Office	
	Telephone No.	
	E-Mail Address:	
7	PAN No.	
8	GST Registration No. (if any)	
9	Proof of Address at State of Consignee for availing local purchase preference	4
10	Give details of the major similar contracts handled by the tendering Company / Firm /Agency during the last three years (attach copy)	
10	Additional information, if any (Attach separate sheet, if required)	

स्थान/ Place: दिनांक/ Date:

जीबनफूकननगर,पोस्टऑफिस-सी.आर.बिल्डिंग,

डिब्र्गढ,असम-786003 दूरभाष: 0373-2950536

ई मेल:<u>ubd-cwc-asm@nic.in/</u> ubddbrcwc@gmail.com

७जल संरक्षण-स्रक्षित भविष्य**७**

अधिकृत व्यक्ति के हस्ताक्षर/ Sign of Authorized person: अधिकृत व्यक्ति का नाम/ Name of Authorized person:



Jibon Phukan Nagar,P.O:C.R. Building, Dibrugarh, Assam - 786003 Tel: 0373-2950536

E-mail: <u>ubd-cwc-asm@nic.in/ubddbrcwc@gmail.com</u>

♦Conserve Water- Save Life

Page 60 f 10

भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग ऊपरीब्रहमप्त्रमंडल, डिब्र्गढ



Government of India Ministry of Jal Shakti Department of Water Resources, RD & GR Central Water Commission Upper Brahmaputra Division, Dibrugarh

Form No:02/फॉर्म संख्या2 -

Bill of Quantity/मात्रा की अनुसूची

Name of Work/ **कार्य का नाम**: "Modification of Level-II Lab at Naharlagun under UBD, CWC, Dibrugarh, Assam during 2024-25"

			Unit	Rate	Amount (Rs.)		
SI N o	Item of Work	Qty	of Qty	per Unit Inc. of GST	In Figures	In Words	
1	Providing and fixing 35mm thick factory made laminated veneer lumber door shutter conforming to IS:14616 and TAD 15:2001 (Part B), fixing with but hinges of required size with necessary screws, all complete as per directions of Engineer-in-charge and paneling with panels of:(Note:-But hinges and necessary screws shall be paid separately). 9.6.2 12mm thick prelaminated particle board (decorative laminated on both sides) grade-1, medium density flat pressed, three layer particle board FPT-I or graded wood particle board FPT-I or graded wood particle board FPT-I, conforming to IS: 3087, bonded with BWP type synthetic resin adhesive as per IS:848 and pre-laminated conforming to IS:12823, Grade 1. Type-II marked	4.42	sqm				
2	False Ceiling Repair:						
4	White Cement (100m length)	20	Kg				
	White Cement application Charge	5	job/				

जीबनफूकननगर,पोस्टऑफिस-सी.आर.बिल्डिंग,

डिब्र्गढ,असम-786003 दूरभाष: 0373-2950536

ई मेल:<u>ubd-cwc-asm@nic.in/</u> ubddbrcwc@gmail.com

♦जल संरक्षण-सुरक्षित भविष्य



Jibon Phukan Nagar,P.O:C.R. Building, Dibrugarh, Assam - 786003 Tel: 0373-2950536

> E-mail: <u>ubd-cwc-asm@nic.in/</u> <u>ubddbrcwc@gmail.com</u>

♦Conserve Water- Save Life

Page 7 of 10

भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग



Government of India Ministry of Jal Shakti Department of Water Resources, RD & GR Central Water Commission Upper Brahmaputra Division, Dibrugarh

ऊपरीब्रहमपुत्रमंडल, डिब्रुगढ

		day					
Aluminium Work:		day					
	159.5	Sa					
	1						9
	-	16					
3							
Cement concrete flooring 1:2:4 (1						-	
-							
	1 9						
,	11.60	cam					
	11.00	Sqiii					
·			7-				
A SECTION OF THE PROPERTY OF T							
			•				
	86		:				
0.08% and conforming to IS:15622,							
of approved brand & manufacturer,							
in all colours and shade, laid on 20							
mm thick cement mortar 1:4 (1							
cement: 4 coarse sand) jointing with							
9	11.60	sqm					
* -							
				*			
				10			
				=			
•		-					
•							
gang saw cut, mirror polished,							
premoulded and prepolished,							
machine cut for kitchen platforms,	0.90	sqm					
vanity counters, window sills, facias							
and similar locations of required							
size, approved shade, colour and							
	cement: 2 coarse sand: 4 graded stone aggregate 12.5 mm nominal size) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 11.3.1 40mm thick with 20mm nominal size stone aggregate Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed Vitrified tiles Matt/Antiskid finish of size 11.41A.3.1 Size of Tile 600 x 600 mm Providing and fixing 18mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required	Installation of aluminium composite panels for partition wall and doors Flooring work for Head and Eye Shower: Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 11.3.1 40mm thick with 20mm nominal size stone aggregate Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed Vitrified tiles Matt/Antiskid finish of size 11.41A.3.1 Size of Tile 600 x 600 mm Providing and fixing 18mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and	Aluminium Work: Installation of aluminium composite panels for partition wall and doors Flooring work for Head and Eye Shower: Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 12.5 mm nominal size) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 11.3.1 40mm thick with 20mm nominal size stone aggregate Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed Vitrified tiles Matt/Antiskid finish of size 11.41A.3.1 Size of Tile 600 x 600 mm Providing and fixing 18mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and	Aluminium Work: Installation of aluminium composite panels for partition wall and doors Flooring work for Head and Eye Shower: Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 11.3.1 40mm thick with 20mm nominal size stone aggregate Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed Vitrified tiles Matt/Antiskid finish of size 11.41A.3.1 Size of Tile 600 x 600 mm Providing and fixing 18mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and	Aluminium Work: Installation of aluminium composite panels for partition wall and doors Flooring work for Head and Eye Shower: Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 11.3.1 40mm thick with 20mm nominal size stone aggregate Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed Vitrified tiles Matt/Antiskid finish of size 11.41A.3.1 Size of Tile 600 x 600 mm Providing and fixing 18mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and	Aluminium Work: Installation of aluminium composite panels for partition wall and doors Flooring work for Head and Eye Shower: Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 11.3.1 40mm thick with 20mm nominal size stone aggregate Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed Vitrified tiles Matt/Antiskid finish of size 11.41A.3.1 Size of Tile 600 x 600 mm Providing and fixing 18mm thick gang saw cut, mirror polished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and	Aluminium Work: Installation of aluminium composite panels for partition wall and doors Flooring work for Head and Eye Shower: Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 11.3.1 40mm thick with 20mm nominal size stone aggregate Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed Vitrified tiles Matt/Antiskid finish of size 11.41.3.1 Size of Tile 600 x 600 mm Providing and fixing 18mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and

जीबनफूकननगर,पोस्टऑफिस-सी.आर.बिल्डिंग,

डिब्र्गढ,असम-786003 दूरभाष: 0373-2950536

ई मेल:<u>ubd-cwc-asm@nic.in/</u> ubddbrcwc@gmail.com

♦जल संरक्षण-सुरक्षित भविष्य♦



Jibon Phukan Nagar,P.O:C.R. Building, Dibrugarh, Assam - 786003

Tel: 0373-2950536

E-mail: <u>ubd-cwc-asm@nic.in/</u> <u>ubddbrcwc@gmail.com</u>

♦Conserve Water- Save Life♦

Page. 8 et 10

भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग ऊपरीब्रहमप्त्रमंडल, डिब्रूगढ



Government of India Ministry of Jal Shakti Department of Water Resources, RD & GR Central Water Commission Upper Brahmaputra Division, Dibrugarh

	texture laid over 20mm thick base cement mortar 1:4 (1 cement: 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc, complete at all levels 8.2.1 Rajnagar Plain White Marble/Udaipur Green Marble/Zebra Black Marble 8.2.1.1 Area of slab upto 0.50 sqm					
7	Plumbing Items:		pc			
	Pipe 20mm	6	рс			
	Elbow 20mm	15	рс			
	Tee 20mm	6	pc			
	Brass elbow	5	pc			
	Brass tee	4	pc			
	Stopcock	1	pc			
	Angle cock	3	pc	v		
	MABT	2	pc		*	
	FABT	2	рс			,
	FWC hindware	1	pc			
	2 in 1 Bibcock	1	pc			
	Hathafacet (Handpusher)	1	pc			
	Connection pipe 2ft	3	pc			
	Wash basin	2	pc	2 × × × × × × × × × × × × × × × × × × ×		
	Western coupling	2	pc			F
	Wash pipe	2	pc			
	White Cement	2	pc			
	T tap	4	pc			
	Pillar cock	2	pc		* u	
	Clip 20mm	20	pc			
	Gum 100ml	2	pc			
	PVC pipe 50mm (20ft)	1	pc			
	Elbow 50mm	8	pc		1	
	PVC Gum (500ml)	2	pc			- 1,-1
	Cowel	11	pc	1 1		
	Cistern	1	pc			
	Sink 24x18inch	1	pc			
	Stopcock	, was	pc			.44
	MABT	3	pc			

जीबनफूकननगर,पोस्टऑफिस-सी.आर.बिल्डिंग,

डिब्र्गढ,असम-786003 दूरभाष: 0373-2950536

ई मेल:<u>ubd-cwc-asm@nic.in/</u> <u>ubddbrcwc@gmail.com</u>

♦जल संरक्षण-सुरक्षित भविष्य♦



Jibon Phukan Nagar,P.O:C.R. Building, Dibrugarh, Assam - 786003 Tel: 0373-2950536

E-mail: <u>ubd-cwc-asm@nic.in/ubddbrcwc@gmail.com</u>

♦Conserve Water- Save Life

Page 9 of 10

भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग



Government of India Ministry of Jal Shakti Department of Water Resources, RD & GR Central Water Commission Upper Brahmaputra Division, Dibrugarh

ऊपरीब्रहमपुत्रमंडल, डिब्रुगढ

l (Inclusive of GST) - in Rs (in Fi				Total (Rs.)	
Electrical Charges	1	job	* 1		
Copper Wire	1	coil			
MCB (32 Amp)	3	рс			
Cashing Pin	2	pc			
Cashing (3mtr)	15	pc			
V casing	20	pc			
L casing	20	pc			
Socket (3 pin)	2	рс			
Switch	5	рс	*		
Power Point Pin	2	рс			
Power Point	10	рс			11 Tr 10 (12 11) (13 11 12 12 12 12 12 12 12 12 12 12 12 12
Electrical Items and work:					
Cutlet Point	20	job			
ink	1	job			
Cistern (Q)	1	job			
Tap Point	8	job			
Wash Basin	2	job	•		
W/C	1	job			
Plumbing Charges:					
Silicon	2	kg			
Fevicol	2	kg			
Г. Тар	2	pc			
Shower	1	pc pc	A. L. Salana		

Yours sincerely,

(Name and Designation of Person) Rubber Stamp of the Firm

जीबनफूकननगर,पोस्टऑफिस-सी.आर.बिल्डिंग,

Total (Inclusive of GST) - in Rs (in Words)

डिब्र्गढ,असम-786003 दूरभाष: 0373-2950536

ई मेल:<u>ubd-cwc-asm@nic.in/</u> ubddbrcwc@gmail.com •जन संरक्षण-सुरक्षित भविष्य•



Jibon Phukan Nagar,P.O:C.R. Building, Dibrugarh, Assam - 786003 Tel: 0373-2950536

E-mail: <u>ubd-cwc-asm@nic.in/ubddbrcwc@gmail.com</u>

Page 10 of 10